

1 LOCATION OF WATER WELL:		Fraction		Township Number	Range Number	
County: Sedgwick		NE ¼ NE ¼ SE ¼		4	T 28 S	R 1 EW
Distance and direction from nearest town or city street address of well if located within city?						
NW corner of Jump & Hydraulic Street						
2 WATER WELL OWNER:		AAA Pawn & Loan				
RR#, St. Address, Box # :		2855 Hydraulic				
City, State, ZIP Code :		Wichita, Ks.				
		Board of Agriculture, Division of Water Resources Application Number:				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 20 ft. ELEVATION: NA				
1 Mile scale bar		Depth(s) Groundwater Encountered 1. 14 ft. 2. _____ ft. 3. _____ ft.				
		WELL'S STATIC WATER LEVEL 12.53 ft. below land surface measured on mo/day/yr 12-27-93				
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm				
		Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm				
		Bore Hole Diameter. 7 5/8 in. to 20 ft., and _____ in. to _____ ft.				
		WELL WATER TO BE USED AS:				
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only (10) Monitoring well				
		Was a chemical/bacteriological sample submitted to Department? Yes..... No X If yes, mo/day/yr sample was submitted				
		Water Well Disinfected? Yes _____ No X				
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued _____ Clamped _____				
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile Welded _____				
(2) PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below) Threaded X				
Blank casing diameter 2 in. to 9 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.						
Casing height above land surface 0 in., weight _____ lbs./ft. Wall thickness or gauge No. sch. 40						
TYPE OF SCREEN OR PERFORATION MATERIAL:		(7) PVC				
1 Steel 3 Stainless steel 5 Fiberglass		10 Asbestos-cement				
2 Brass 4 Galvanized steel 6 Concrete tile		8 RMP (SR) 11 Other (specify)				
		9 ABS 12 None used (open hole)				
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)				
1 Continuous slot (3) Mill slot		6 Wire wrapped 9 Drilled holes				
2 Louvered shutter 4 Key punched		7 Torch cut 10 Other (specify)				
SCREEN-PERFORATED INTERVALS:		From 9 ft. to 19 ft., From ft. to ft.				
		From ft. to ft., From ft. to ft.				
GRAVEL PACK INTERVALS:		From 7.5 ft. to 19 ft., From ft. to ft.				
		From ft. to ft., From ft. to ft.				
6 GROUT MATERIAL:		1 Neat cement (2) Cement grout (3) Bentonite 4 Other				
Grout Intervals: From 0 ft. to 5.5 ft., From 5.5 ft. to 7.5 ft., From ft. to ft.						
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well				
1 Septic tank 4 Lateral lines 7 Pit privy (11) Fuel storage		15 Oil well/Gas well				
2 Sewer lines 5 Cess pool 8 Sewage lagoon		12 Fertilizer storage 16 Other (specify below)				
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		13 Insecticide storage				
Direction from well? NA		How many feet? excavation				
LITHOLOGIC LOG		PLUGGING INTERVALS				
FROM	TO				FROM	TO
0	5"	concrete				
5"	5'	clay, v dk brn, v slty, tr v f snd, semiplst				
5	8	clay, v sandy, f grnd, lt grn-gry, v slty				
8	12	sand, v f-med grnd, v well strd, yell-brn in clr				
12	15	sand, v f-med grn, v well strd, lt gry in clr				
15	20	sand, v f-c grnd, mod-v grvly, prly strd, yell-brn to lt gry				
		AMW1-flush mount cover				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-20-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 01-20-94 under the business name of GeoCore Services, Inc. by (signature) <i>Dale P... ..</i>						