

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		SW 1/4 NW 1/4 NE 1/4	14	T 28 S	R 1 EXX
Distance and direction from nearest town or city street address of well if located within city? Approximately 1/8 mile south and 1/8 mile east of Wichita					
2 WATER WELL OWNER: Boeing Company					
RR#, St. Address, Box # : 3801 S. Oliver					
City, State, ZIP Code : Wichita, KS 67210					
Board of Agriculture, Division of Water Resources Application Number: N/A					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 35 ft. ELEVATION: unknown			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 11.8 ft. below land surface measured on mo/day/yr 8-25-92			
		Pump test data: Well water was not ch'd ft. after hours pumping gpm			
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 11 in. to 35 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Recovery			
Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes No X					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped					
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded					
7 Fiberglass Threaded					
Blank casing diameter 5 in. to 13 ft., Dia. in. to ft., Dia. in. to ft.					
Casing height above land surface 24 in., weight 2.87 lbs./ft. Wall thickness or gauge No. 265					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)					
9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 13 ft. to 33 ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 11 ft. to 35 ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug					
Grout Intervals: From ft. to ft., From ft. to ft., From 0 ft. to 11 ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
13 Insecticide storage Ground already contaminated					
Direction from well? How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	7	Fill, clay and sand mixed			
7	10	Clay, tan with caliche and some sand mixed			
10	14	Clay, tan with caliche			
14	16.5	Streaks of sand and streaks of clay, tan			
16.5	20	Sand, fine, some gravel, fine with clay streaks, loose, silty			
20	20.5	Cemented sand, very hard			
20.5	32	Clay, green, yellow, red with thin streak of green limestone at 22.5' with thin streak of sand and cobble at 27' with thin streak of limestone, brown at 28'			
32	35	Shale, gray, soft			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-18-92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 2-24-93 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>					