

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		SW ¼ NE ¼ SW ¼	14	T 28 S	R EW
Distance and direction from nearest town or city street address of well if located within city? West of K-15, 3720 Feet South of MacArthur, Wichita, Kansas					
2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP Code :		Boeing Commercial Airplane Group P.O. Box 7730 Wichita, Kansas 67277-7730 Board of Agriculture, Division of Water Resources Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 52 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 40 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 33.7 ft. below land surface measured on mo/day/yr 12-14-92 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter in. to ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only ⑩ Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No ✓ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile Welded			
② PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below) Threaded ✓			
Blank casing diameter 2 in. to 25 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 35 in., weight lbs./ft. Wall thickness or gauge No. Sch. 80					
TYPE OF SCREEN OR PERFORATION MATERIAL:		⑦ PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot ③ Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 27 ft. to 52 ft., From ft. to ft.					
		From ft. to ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From 25 ft. to 52 ft., From ft. to ft.					
		From ft. to ft., From ft. to ft.			
6 GROUT MATERIAL: ① Neat cement 2 Cement grout ③ Bentonite 4 Other					
Grout Intervals: From 23 ft. to 25 ft., From Surf ft. to 23 ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage ⑬ Other (specify below)		Boeing industrial plant			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 4000					
Direction from well? northeast		How many feet?			
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS					
0	5	Medium to dark brown clay			MW125
5	15	Red silty clay			
15	25	Red brown silty clay			
25	27	Brown silty clay			
27	32	Fine to coarse sand			
32	45	Medium to coarse sand/gravel			
45	48	Olive gray weathered shale			
48	52	Dark gray shale, competent			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ⑪ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-03-92 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 01-09-93					
under the business name of GeoCore Services, Inc. by signature Dan A. Bell					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					

F

54

1/4

4