

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		NW ¼ NW ¼ SE ¼	14	T 28 S	R 1 EW
Distance and direction from nearest town or city street address of well if located within city?					
Technology & Quality Drives					
2 WATER WELL OWNER: Boeing Commercial Airplane Group RR#, St. Address, Box #: Box 7730 Board of Agriculture, Division of Water Resources City, State, ZIP Code : Wichita, Kansas 67277-7730 Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N ----- NW NE SW SE ----- S E (Diagram showing section box with X in center)		4 DEPTH OF COMPLETED WELL.....35.5 ft. ELEVATION: Depth(s) Groundwater Encountered 1..26 ft. 2.....ft. 3.....ft. WELL'S STATIC WATER LEVEL NA ft. below land surface measured on mo/day/yr Pump test data: Well water wasft. after hours pumping gpm Est. Yield gpm: Well water wasft. after hours pumping gpm Bore Hole Diameter 7 7/8 in. to 45 ft., andin. toft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only ⑩ Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X			
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped ② PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter2....in. to10.5....ft., Dia.....in. toft., Dia.....in. toft. Casing height above land surface.....36....in., weight.....lbs./ft. Wall thickness or gauge No. Sch. 80 Threaded.....X					
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass ⑦ PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot ③ Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From.....10.5....ft. to35.5....ft., From.....ft. toft. GRAVEL PACK INTERVALS: From.....9....ft. to35.5....ft., From.....ft. toft. From.....ft. toft., From.....ft. toft.					
6 GROUT MATERIAL: 1 Neat cement ② Cement grout ③ Bentonite 4 Other Grout Intervals: From.....0....ft. to2....ft., From.....2....ft. to9....ft., From.....ft. toft.					
What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage ⑯ Other (specify below) Boeing industrial plant Direction from well? unknown How many feet? unknown					
FROM		TO		LITHOLOGIC LOG	PLUGGING INTERVALS
0	2			Dark brown clay	MW137
2	5			Dark medium red brown clay	
5	25			Red brown silty clay	
25	30			Olive gray silty clay	
30	34.5			Olive gray shale	
34.5	35.5			Dark gray shale	
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (#) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 02-03-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/year) 02-08-93 by (signature) Dale Abbott under the business name of GeoCore Services, Inc.					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					