


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction SW NW SW SE 1/4 SW 1/4 SE 1/4	Section number 17	Township number T 28 S	Range number R 1E E/W
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: R.R. or street: City, state, zip code:			
4645 Palisade Wichita, Kansas			Marble Products 4645 Palisade Wichita, Kansas			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 11 in. Completion date 6-23-78 Well depth 45 ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other
Topsoil		0		3		9. Casing: Material styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 45 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gage No. 200
Clay		3		10		10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/gap .06 Length 20' Set between 25 ft. and 45 ft. ft. and ☐ ft.
Fine Sand		10		23		Gravel pack? yes Size range of material 1/4-1/8"
Medium Sand		23		29		11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 6-23-78
Coarse Sand		29		45		12. Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
						13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date ☐
						14. Well head completion: ☐ Pitless adapter 12 inches above grade
						15. Well grouted? yes 1-2 Fine Sand Mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.
						16. Nearest source of possible contamination: City ft. 200 Direction North Type Sewer Well disinfected upon completion? ☒ Yes ☐ No
						17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
						(Use a second sheet if needed)
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		Flat Ground		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Ornell Date 7-6-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5