

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 1/4 NW 1/4	Section number 19	Township number T 28	Range number S R 1	E/A																															
2. Distance and direction from nearest town or city: 1 mile SW of Wichita			3. Owner of well: Mr. Lee Cox R.R. or street: Wichita, Kansas City, state, zip code:																																		
4. Locate with "X" in section below: Well No. 1			6. Bore hole dia. 30 in. Completion date 4/12/76 Well depth 55 ft.																																		
5. Type and color of material			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary																																		
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																		
			9. Casing: Material Stl Height: Above of below Threaded ☐ Welded ☒ Surface 24 in. RMP ☐ PVC ☐ Weight 36.91 lbs./ft. Dia. 16 in. to 31 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 219																																		
			10. Screen: Manufacturer's name Doerr Metal Products Type Stl. Dia. 16" Slot/gauze 1/8" Length 24' Set between 31 ft. and 55 ft. Gravel pack? Yes Size range of material 1/8 x 1/2																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;"></th> <th style="width: 20%;">From</th> <th style="width: 20%;">To</th> </tr> </thead> <tbody> <tr><td>Sandy Soil</td><td>0</td><td>3</td></tr> <tr><td>Brown clay</td><td>3</td><td>11</td></tr> <tr><td>Med. to coarse sand & med. gravel</td><td>11</td><td>41</td></tr> <tr><td>Med. to coarse sand & fine gravel</td><td>41</td><td>53</td></tr> <tr><td>Green and blue shale</td><td>53</td><td></td></tr> <tr><td> </td><td></td><td></td></tr> <tr><td> </td><td></td><td></td></tr> <tr><td> </td><td></td><td></td></tr> <tr><td> </td><td></td><td></td></tr> <tr><td> </td><td></td><td></td></tr> </tbody> </table>				From	To	Sandy Soil	0	3	Brown clay	3	11	Med. to coarse sand & med. gravel	11	41	Med. to coarse sand & fine gravel	41	53	Green and blue shale	53																	11. Static water level: 11 ft. below land surface Date 4/12/76	
				From	To																																
			Sandy Soil	0	3																																
			Brown clay	3	11																																
			Med. to coarse sand & med. gravel	11	41																																
			Med. to coarse sand & fine gravel	41	53																																
			Green and blue shale	53																																	
12. Pumping level below land surfaces: 22 ft. after 3 hrs. pumping 600 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 800 g.p.m.																																					
13. Water sample submitted: ☐ Yes ☒ No Date ☐																																					
14. Well head completion: 24 inches above grade ☐ Pitless adapter																																					
15. Well grouted? yes With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.																																					
16. Nearest source of possible contamination: none ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☐ No																																					
17. Pump: ☐ Not installed Manufacturer's name Layne & Bowler Model number 10KEN HP 60 Volts — Length of drop pipe 40 ft. capacity 600 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																					
18. Elevation:			19. Remarks:																																		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita License No. Kansas Address Wichita, Kansas Signed [Signature] Date 4/12/76 Authorized representative																																		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5