


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedgewick</u>	Fraction <u>SE 1/4 NE 1/4 NE 1/4</u>	Section number <u>26</u>	Township number <u>T 28 S</u>	Range number <u>R 10 E</u>
2. Distance and direction from nearest town or city:		3. Owner of well: <u>Joe Goad</u>				
Street address of well location if in city:		R.R. or street: <u>R# 2 Box 111</u>				
<u>4000 E 57th South Derby</u>		City, state, zip code: <u>Derby KS 67037</u>				
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>5 1/2</u> in. Completion date <u>10/24/78</u>		
		<u>Septic</u>		Well depth <u>50</u> ft.		
5. Type and color of material		From To		7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dog		
<u>Top Soil.</u>		<u>0 2</u>		☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
<u>red clay.</u>		<u>2 28</u>		8. Use: ☒ Domestic ☐ Public supply ☐ Industry		
<u>med to coarse gravel</u>		<u>28 48</u>		☐ Irrigation ☐ Air conditioning ☐ Stock		
<u>charcoal clay.</u>		<u>48 50</u>		☐ Law ☐ Oil field water ☐ Other		
				9. Casing: <u>Steel</u> Height <u>12</u> Above or below		
				Threaded <u>Welded</u> Surface <u>12</u> in.		
				RMP <u>X</u> PVC <u>Weight</u> <u>11.50</u> lbs./ft.		
				Dia. <u>5</u> in. to <u>50</u> ft. depth Wall Thickness: inches or		
				Dia. <u>5</u> in. to <u>50</u> ft. depth gage No. <u>200</u>		
				10. Screen: Manufacturer's name <u>Sanflow</u>		
				Type <u>200</u> Dia. <u>5 in</u>		
				Plot/gauze <u>1/16</u> Length <u>10 ft</u>		
				Set between <u>40</u> ft. and <u>50</u> ft.		
				Gravel pack? <u>Yes</u> Size range of material <u>3/8</u>		
				11. Static water level: <u>31</u> ft. below land surface Date <u>10/24/78</u>		
				12. Pumping level below land surfaces:		
				<u>35</u> ft. after <u>15</u> hrs. pumping <u>15</u> g.p.m.		
				<u>15</u> ft. after <u>15</u> hrs. pumping <u>15</u> g.p.m.		
				Estimated maximum yield <u>15-25</u> g.p.m.		
				13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>10/24/78</u>		
				14. Well head completion: <u>12</u> inches above grade		
				☐ Pitless adapter <u>12</u> inches above grade		
				15. Well grouted? <u>Yes</u>		
				With: <u>Neat cement</u> ☒ Bentonite ☒ Concrete ☒		
				Depth: From <u>31</u> ft. to <u>13</u> ft.		
				16. No test source of possible contamination: <u>100</u> ft. Direction <u>NE</u> Type <u>Septic</u>		
				Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed		
				Manufacturer's name <u>Sanflow</u>		
				Model number <u>318</u> HP <u>1/2</u> Volts <u>115</u>		
				Length of drop pipe <u>31</u> ft. capacity <u>15</u> g.p.m.		
				Type: ☐ Submersible ☐ Turbine		
				☐ Jet ☐ Reciprocating		
				☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:				
Topography: <u>X</u> Hill <u>X</u> Slope <u>X</u> Upland <u>X</u> Valley		<u>Customer to furnish 4'x4'x4" slab around well at grade</u>				
		<u>Per State Regulations</u>				
		<u>Signed Joe Goad</u>				
		20. Water well contractor's certification: <u>Winnings Bully 318</u>				
		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.				
		Business name <u>Sedgewick KS</u> License No. <u>318</u>				
		Address <u>Derby KS</u> Date <u>10/24/78</u>				
		Signed <u>Joe Goad</u> Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5