


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction SW NE NE	Section number 29	Township number T 28	Range number S 1 R 1 E
2. Distance and direction from nearest town or city:			3. Owner of well: WAYNE HANCOCK			
Street address of well location if in city: 418 W. 59TH. SO. WICHITA KANS.			R.R. or street: 418 W. 59TH. SO.			
			City, state, zip code: WICHITA KANS. 67217			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 9 in. Completion date 6-12-79		
		DRILLED 9" HOLE TO 11.5 FT. INSTALLED CASING + COMPLETED WITH SAND BUCKET AT 39'		Well depth 39 ft. FROM GRADE		
5. Type and color of material		From	To	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☐ Reverse rotary		
BROWN SANDY SOIL		0	2.5	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
CLAY GRAY		2.5	5	Casing: Material RMP Height Above or below		
SAND FINE GRAY		5	8	Threading Welded ☒ Surface 12 in.		
SAND FINE TAN		8	9	RMP ☒ PVC ☐ Weight 1.55 lbs./ft.		
SAND FINE GRAY		9	10	Dia. 5 in. to 40 ft. depth Wall Thickness 0.200 inches or		
CLAY GRAY		10	11	Dia. 5 in. to 40 ft. depth gage No. 0200		
SAND MEDIUM TAN		11	20	10. Screen: Manufacturer's name SANFLOWER		
CLAY GRAY		20	21	Type RMP Dia. 5 INCH		
SAND COARSE GRAVEL BROWN		21	24	Slot/gauze 0.31 Length 6 FT.		
SAND MED. TAN		24	30	Set between 33 ft. and 39 ft.		
SAND COARSE TAN		30	39	Grovel pack? NO Size range of material		
				11. Static water level: 11.5 ft. below land surface Date 6-12-79		
				12. Pumping level below land surfaces: NA g.p.m.		
				Estimated maximum yield 70 g.p.m.		
				13. Water sample submitted: NO Date		
				14. Well head completion: 12 inches above grade		
				15. Well grouted? YES		
				With: ☒ Neat cement ☒ Bentonite ☒ Concrete		
				Depth: From 0 ft. to 11.5		
				16. Nearest source of possible contamination: CAST IRON		
				ft. 35 Direction N.E. Type SEWER		
				Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed		
				Manufacturer's name		
				Model number HP Volts		
				Length of drop pipe ft. capacity g.p.m.		
				Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation: 1300'		19. Remarks: OWNER WILL CONSTRUCT 4' X 4' X 4' SLAB AROUND WELL		20. Water well contractor's certification: BEARDEN PUMP & WELL		
Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
				Business name BEARDEN PUMP & WELL		
				Address 3142 MENTOR WICHITA KANS.		
				Signed Otis W. Bearden Date 6/18/79		
				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5