

[1] LOCATION OF WATER WELL:		Fraction	Township Number	Range Number
County: Sedgwick		NW ¼ NW ¼ SW ¼	Section Number 31	T 28 S R 1E EW
Distance and direction from nearest town or city street address of well if located within city? 410 Apple Lane Haysville,Ks.				
[2]	WATER WELL OWNER: Stan Johnson		Board of Agriculture, Division of Water Resources	
RR#, St. Address, Box # : City, State, ZIP Code :		410 Apple Lane Haysville,Ks.	Application Number:	
[3]	LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			
A square divided into four smaller squares by dashed lines. The top-left square is labeled 'NW', top-right 'NE', bottom-left 'SW', and bottom-right 'SE'. A small 'x' is drawn in the center of the 'SW' square.		[4] DEPTH OF COMPLETED WELL.....50..... ft. ELEVATION:		
		Depth(s) Groundwater Encountered 1.....25.....ft. 2.....ft. 3.....ft. WELL'S STATIC WATER LEVEL 25 ft. below land surface measured on mo/day/yr .. 5-30-89 .. Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter.... 11...in. toft., and.....in. toft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes.....No.. X.....; If yes, mo/day/yr sample was sub- mitted		
[5] TYPE OF BLANK CASING USED:				
Blank casing diameter 5in. to ... 30ft., Diain. toft., Diain. toft.				
Casing height above land surface..... 12in., weight 1.59 lbs./ft. Wall thickness or gauge No.203				
CASING JOINTS: Glued .. X .. Clamped Welded Threaded				
TYPE OF SCREEN OR PERFORATION MATERIAL:				
SCREEN OR PERFORATION OPENINGS ARE:				
SCREEN-PERFORATED INTERVALS: From.....30.....ft. to50.....ft., From.....ft. to.....ft.				
GRAVEL PACK INTERVALS: From.....24.....ft. to50.....ft., From.....ft. to.....ft.				
[6] GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other				
Grout Intervals: From...4.....ft. to ... 24ft., From.....ft. to.....ft., From.....ft. to.....ft.				
What is the nearest source of possible contamination:				
Direction from well? East How many feet? 75 PLUGGING INTERVALS				
FROM	TO	LITHOLOGIC LOG	FROM	TO
0	3	topsoil		
3	25	clay		
25	32	fine sand		
32	45	medium sand		
45	50	grey shale		
[7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-30-89 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This Water Well Record was completed on (mo/day/yr) 6-1-89 under the business name of Harp Well and Pump Service, Inc. by (signature)				