


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NW 1/4 NW 1/4	Section number 36	Township number T 28 S R 1 E 1/4	Range number	
2. Distance and direction from nearest town or city: Street address of well location if in city: 6440 S.E. Blvd. Derby, Kansas			3. Owner of well: R.R. or street: David Short 6440 S.E. Blvd. Derby, Kansas City, state, zip code:				
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 				
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 11-17-76 Well depth 59 ft.		
Sandy Topsoil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
Clay			2	40	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Fine Sand			40	41	9. Casing: Material styrene Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC Weight ☐ lbs./ft. Dia. 5 in. to 59 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200		
Clay			41	45	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot 0.06 Length 20' Set between 39 ft. and 59 ft. Gravel pack? yes Size range of material 1-1/8"		
Blue Shale			45	59	11. Static water level: 30 ft. below land surface Date 11-17-76 mo./day/yr.		
					12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.		
					13. Water sample submitted: Yes No Date		
					14. Well head completion: 12 well seal Pitless adapter 12 inches above grade		
					15. Well grouted? yes With: Neat cement Bentonite ☒ Concrete Depth: From 40 ft. to 14 ft.		
					16. Nearest source of possible contamination: Septic ft. 50 Direction SW Type Tank Well disinfected upon completion? ☒ Yes ☐ No		
					17. Pump: Not installed Manufacturer's name Sta-Rite Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 45 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:			19. Remarks: Well and pump inside well house.			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 2-12-77 Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5