

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: SEDGWICK 087		NE 1/4 NE 1/4 NE 1/4	4	T 28 S	R 1 E/W
Distance and direction from nearest town or city street address of well if located within city? 1535 E. PAWNEE WICHITA, KANSAS					
2 WATER WELL OWNER:		FINA OIL & COMPANY		Board of Agriculture, Division of Water Resources	
RR#, St. Address, Box #		P.O. BOX 2159 DALLAS, TEXAS 75221		Application Number:	
City, State, ZIP Code					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 26 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 17 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 17 ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 7 1/4 in. to 26 ft. and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering ☒ Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well <u>Spargers Point</u>			
		Was a chemical/bacteriological sample submitted to Department? Yes No If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		Welded			
☒ PVC 4 ABS		Threaded			
Blank casing diameter 2 in. to ft. Dia		in. to ft. Dia			
Casing height above land surface -3 in. weight Sch 40		lbs./ft. Wall thickness or gauge No.			
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot ☒ Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)			
SCREEN-PERFORATED INTERVALS:		From 26 ft. to 24 ft. From ft. to ft. From ft. to ft. From ft. to ft.			
GRAVEL PACK INTERVALS:		From 26 ft. to 22 ft. From ft. to ft. From ft. to ft. From ft. to ft.			
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout ☒ Bentonite 4 Other Grout Intervals: From 18 ft. to 0.6 ft. From 22 ft. to 18 ft. From ft. to ft.			
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well 1 Septic tank 4 Lateral lines 7 Pit privy ☒ Fuel storage 15 Oil well/Gas well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage			
Direction from well? SW		How many feet? 75'			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	6"	Concrete			
6"	3'	Top soil			
3'	9'	Blue Clay			
9'	14'	Fine Sand			
14'	20'	Med Sand			
20'	26'	Med To Coarse Sand			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 1-17-95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 575 This Water Well Record was completed on (mo/day/yr) 2-14-95 under the business name of KURTZ ENVIRONMENTAL SERVICE by (signature) M.H.					