


1 LOCATION OF WATER WELL: County: Sedgwick Fraction: SE 1/4 NW 1/4 NW 1/4 Section Number: 11 Township Number: T 28 S Range Number: R 2 E
Distance and direction from nearest town or city street address of well if located within city?
600 East of 31st & 127th E, Wichita RW-1d

2 WATER WELL OWNER: Conoco, Inc. Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: P.O. Box 2197 Application Number:
City, State, ZIP Code: Houston, Texas 77252

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  4 DEPTH OF COMPLETED WELL: 58.5 ft. ELEVATION: 1011.92
Depth(s) Groundwater Encountered 1. 31 ft. 2. ft. 3. ft.
WELL'S STATIC WATER LEVEL 31 ft. below land surface measured on mo/day/yr 10/1/92
Pump test data: Well water was ft. after hours pumping gpm
Est. Yield gpm: Well water was ft. after hours pumping gpm
Bore Hole Diameter 8 in. to 59 ft. and in. to ft.
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Recovery well
Was a chemical/bacteriological sample submitted to Department? Yes No Y If yes, mo/day/yr sample was submitted
Water Well Disinfected? Yes No Y

5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded
Blank casing diameter 4" in. to 45.9 ft. Dia. in. to ft. Dia. in. to ft.
Casing height above land surface 36 in. weight 2.0 lbs./ft. Wall thickness or gauge No. Sen 40
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 10 Other (specify)
7 Torch cut
SCREEN-PERFORATED INTERVALS: From 45.9 ft. to 58.5 ft. From ft. to ft.
GRAVEL PACK INTERVALS: From 43.0 ft. to 58.5 ft. From ft. to ft.
From ft. to ft. From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other hole plug
Grout Intervals: From 40 ft. to 43 ft. From 3 ft. to 43 ft. From 0 ft. to 3 ft.
What is the nearest source of possible contamination: 10 Livestock pens 14 Abandoned water well
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage Petroleum Pipeline
Direction from well? West How many feet? 350'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5.0	Clay			
5.0	52.0	Weathered Shale			
52.0	53.0	Red bed			
53.0	58.0	Weathered shale			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 9/30/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 517 This Water Well Record was completed on (mo/day/yr) 10/7/92 under the business name of Groundwater Technology, Inc. by (signature) Steven R. Hutchins