

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County SEDGWICK	Fraction 1/4 SE 1/4 NW 1/4	Section number 34	Township number T 28 S R 2E E/W	Range number						
2. Distance and direction from nearest town or city: 6614 Lynnrae Wichita, Kansas			3. Owner of well: Wayne Williams Real Estate R.R. or street: 535 No. Oliver City, state, zip code: Wichita, Kansas								
4. Locate with "X" in section below: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td>NW</td><td>NE</td></tr><tr><td style="text-align: center;">X</td><td></td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile			NW	NE	X		SW	SE	Sketch map:		
NW	NE										
X											
SW	SE										
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date _____ Well depth 75 ft. 6-30-78						
Topsoil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary						
Brown Clay			2	18	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other						
Light Tan Shale(Soft)			18	26	9. Casing: Material Styrene Height: Above or below _____ Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight _____ lbs./ft. Dia. 5 in. to 75 ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth gage No. .200						
Blue Shale(Soft)			26	70	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/gage .06 Length 40' Set between 35 ft. and 75 ft. ft. and _____ ft. Gravel pack? yes Size range of material 1/4-1/8"						
Blue Shale Mixed with White Limestone			70	75	11. Static water level: _____ mo./day/yr. 30 ft. below land surface Date 6-30-78						
					12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.						
					13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____						
					14. Well head completion: ☒ Pitless adapter 12 Inches above grade						
					15. Well grouted? yes 1-2 Fine Sand Mix With: _____ Neat cement _____ Bentonite ☒ Concrete _____ Depth: From 40" ft. to 14 ft.						
					16. Nearest source of possible contamination: ft. _____ Direction _____ Type NONE Well disinfected upon completion? ☒ Yes ☐ No						
					17. Pump: _____ Not installed Manufacturer's name Sta-Rite Model number 8P4C0 HP 1/2 Volts 230 Length of drop pipe 67 ft. capacity 8 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other						
(Use a second sheet if needed)											
18. Elevation: Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley	19. Remarks: Septic system not installed at this time. No apparent source for contamination.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. 67209 Address Wichita, Kansas Signed M. Arnold Date 6-2-78 Authorized representative								

28
20
34
Sec
1/4
1/4
1/4
1/4
SE NW