

# WELL RECORD

22-28-20 32-28-20E

Well No. 1. Farm Erney Producer Wayne E. Wild  
 Location \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ Rg. \_\_\_\_\_  
 Elevation \_\_\_\_\_ State Kansas County Neosho  
 Kind (Oil, Gas, Water, Dry Hole) Dry Hole Contractor Evans & Son.  
 Producing formation None Top \_\_\_\_\_ Bottom \_\_\_\_\_  
 Shot with \_\_\_\_\_ qts. \_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_  
 Packer Set at \_\_\_\_\_ Kind \_\_\_\_\_ Size \_\_\_\_\_  
 Liner \_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ Perforated from \_\_\_\_\_ to \_\_\_\_\_

## LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
4	topsoil	4			
11	sandrock	15			
10	lime	25			
35	lime broken	55			
21	lime	71			
46	shale	117			
28	lime	145			
8	slate blk.	153	- water		
72	shale	225			
10	sand & lime	235			
2	shale	237			
8	lime	245			
65	shale	310			
46	lime 40'	356			
46	shale d. gas.	402			
21	lime 20'	423			
7	shale d.	430	- water		
5	lime 5'	435			
4	shale d.	439			
78	shale sandy	517			
2	lime 2'	519			
23	shale	542			
2	lime	544			
6	shale blk.	550			
44	shale	594			
41	shale sandy	635			
15	light shale	649			
11	white shale	660			
6	red bed	666	td.		

Total Depth 666'  
 Open Hole \_\_\_\_\_  
 Casing 8" drivepipe at 11' cemented  
 Casing 7" at 472' 6" pulled.  
 Casing \_\_\_\_\_ at \_\_\_\_\_  
 Cement \_\_\_\_\_  
 Tubing \_\_\_\_\_  
 Rods \_\_\_\_\_  
 Additional Information This well was  
saved for a water well. Put 100'  
mud on bottom, run 3 sacks of  
cement on mud. Set rock bridge  
at 200', run 6 sacks of cement on  
bridge. Drivepipe was cemented  
with 2 sacks.

*611-613 light  
 Oil odor, dark sand  
 did not wash.*

KEAS DONATION

SEPTEMBER 1991

Date Completed November 19, 1955 O. K. Jim Evans Jr.  
Superintendent