

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Butler	Fraction CW 1/4 SE 1/4 SE 1/4	Section number 21	Township number T 28 S R 3	Range number 3	EW
2. Distance and direction from nearest town or city: 2N 2 3/4 E				3. Owner of well: Jerry Crow			
Street address of well location if in city: Rosehill Kans				City, state, zip code: Derby Kansas			
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. 10 in. Completion date 6-25-76		
					Well depth 110 ft.		
					7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
					8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
					9. Casing: Material plastic Height: Above or below Threaded ☐ Welded gl Surface 15 in. RMP ☒ PVC gl Weight 175 lbs./ft. Dia. 6 in. to 110 ft. depth Wall Thickness: inches or Dia. 6 in. to 110 ft. depth gage No. 175		
5. Type and color of material		From		To		10. Screen: Manufacturer's name g & L	
Red Clay		0		6		Type RMP Dia. 6	
yellow lime		6		17		Slot gauge 1/16 Length 20 ft	
Yellow Clay		17		21		Set between 90 ft. and 110 ft.	
grey lime		21		33		Gravel pack? no Size range of material _____	
grey shale		33		55		11. Static water level: _____ mo./day/yr.	
yellow lime		55		88		75 ft. below land surface Date 6-25-1976	
grey shale		88		94		12. Pumping level below land surfaces:	
water		94				_____ ft. after _____ hrs. pumping _____ g.p.m.	
grey lime		94		110		_____ ft. after _____ hrs. pumping _____ g.p.m.	
						Estimated maximum yield 20 g.p.m.	
						13. Water sample submitted: _____ mo./day/yr.	
						Yes ☒ No ☐ Date _____	
						14. Well head completion:	
						☒ Pitless adapter 15 inches above grade	
						15. Well grouted? yes	
						With: ☒ Neat cement ☐ Bentonite ☐ Concrete	
						Depth: From 13 ft. to 3 ft.	
						16. Nearest source of possible contamination:	
						ft. 140 Direction NW Type oil well	
						Well disinfected upon completion? ☒ Yes ☐ No	
						17. Pump: _____ Not installed	
						Manufacturer's name Houder	
						Model number 105J HP 3/4 Volts 230	
						Length of drop pipe 100 ft. capacity 10 g.p.m.	
						Type:	
						☒ Submersible ☐ Turbine	
						☐ Jet ☐ Reciprocating	
						☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks:		20. Water well contractor's certification:			
Topography:		owner will put on slab.		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.			
☐ Hill				Wike well drilling 122			
☐ Slope				Business name _____ License No. _____			
☒ Upland				Address Rt 3 Box 1282 Augusta Kansas			
☐ Valley				Signed W. W. Wike Date 6-25-76			
		Jerry L. Crow		Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5