

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Butler		SE 1/4 NW 1/4 NW 1/4		29		T 28 S		R 3 E EW	
Distance and direction from nearest town or city street address of well if located within city?									
Rose Hill 2 North 1/4 East South into									
2 WATER WELL OWNER:		R.M. Johnson							
RR#, St. Address, Box # :		Box 385							
City, State, ZIP Code :		Rose Hill, Kansas 67133							
		Board of Agriculture, Division of Water Resources Application Number:							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 60 ft. ELEVATION:							
		Depth(s) Groundwater Encountered 1. 28/35 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL: G.L. * ft. below land surface measured on mo/day/yr 5/19/87 Pump test data: Well water was 13 ft. after 2 hours pumping 40 gpm Est. Yield 50/60 gpm: Well water was 20 ft. after 5 hours pumping 45 gpm Bore Hole Diameter: 8 in. to t.d. ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial (7 Lawn and garden only) 9 Dewatering 12 Other (Specify below) Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded (2-PVC) 4 ABS 7 Fiberglass Threaded							
Blank casing diameter 5 in. to ft., Dia.		in. to ft., Dia.							
Casing height above land surface 38 in., weight		lbs./ft. Wall thickness or gauge No. SDR 26							
TYPE OF SCREEN OR PERFORATION MATERIAL:		1 Steel 3 Stainless steel 5 Fiberglass (7 PVC) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		1 Continuous slot 3 Mill slot 5 Gauzed wrapped (8 Saw cut) 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS:		From 28 ft. to 33 ft., From 53 ft. to 58 ft. From ft. to ft., From ft. to ft.							
GRAVEL PACK INTERVALS:		From -20 ft. to t.d. ft., From ft. to ft. From ft. to ft., From ft. to ft.							
6 GROUT MATERIAL: (1 Neat cement)		2 Cement grout 3 Bentonite 4 Other Grout Intervals: From G.L. ft. to 20 ft., From ft. to ft., From ft. to ft.							
What is the nearest source of possible contamination:		1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well (3 Watertight sewer lines) 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? East How many feet? 65							
FROM	TO	LITHOLOGIC LOG		FROM	TO	LITHOLOGIC LOG			
0	15	Yel sh.							
15	35	Grn/ Blu sh. (water zone)							
35	36	Wht/Gry lm med.							
36	45	Bl sh/ shells sft.							
45	51	Red sh.							
51	53	Hrd. lm. gry.							
53	60	Blu sh/ lm							
60	T.D.								
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-23-87 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 171 This Water Well Record was completed on (mo/day/yr) 5-23-87 under the business name of G & S Drilling by (signature) <i>Edith Johnson</i>									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.									

5910000078-20