

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>Butler</u>	Fraction <u>SE 1/4 NE 1/4 NE 1/4</u>	Section number <u>30</u>	Township number <u>T 28</u>	Range number <u>S 3</u>	E/W <u>1</u>																																	
2. Distance and direction from nearest town or city: <u>1 3/4 N of</u>			3. Owner of well: <u>City of Rose Hill</u>																																				
Street address of well location if in city: <u>Rose Hill</u>			R.R. or street: City, state, zip code: <u>Rose Hill KS</u>																																				
4. Locate with "X" in section below:		Sketch map:		Well # <u>4</u>																																			
				6. Bore hole dia. <u>14</u> in. Completion date <u>4-28-79</u> Well depth <u>58</u> ft.																																			
5. Type and color of material		<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr><td><u>Top Soil</u></td><td><u>0</u></td><td><u>2</u></td></tr> <tr><td><u>Clay brown</u></td><td><u>2</u></td><td><u>6</u></td></tr> <tr><td><u>Clay yellow</u></td><td><u>6</u></td><td><u>12</u></td></tr> <tr><td><u>Alluvium yellow gray (some water)</u></td><td><u>12</u></td><td><u>22</u></td></tr> <tr><td><u>Shale blue gray</u></td><td><u>22</u></td><td><u>30</u></td></tr> <tr><td><u>Shale light gray</u></td><td><u>30</u></td><td><u>37</u></td></tr> <tr><td><u>Limestone yellow brown (water)</u></td><td><u>37</u></td><td><u>44</u></td></tr> <tr><td><u>Shale blue gray</u></td><td><u>44</u></td><td><u>51</u></td></tr> <tr><td><u>Shale light gray</u></td><td><u>51</u></td><td><u>57</u></td></tr> <tr><td><u>Shale Rusty Red</u></td><td><u>57</u></td><td><u>58</u></td></tr> </tbody> </table>			From	To	<u>Top Soil</u>	<u>0</u>	<u>2</u>	<u>Clay brown</u>	<u>2</u>	<u>6</u>	<u>Clay yellow</u>	<u>6</u>	<u>12</u>	<u>Alluvium yellow gray (some water)</u>	<u>12</u>	<u>22</u>	<u>Shale blue gray</u>	<u>22</u>	<u>30</u>	<u>Shale light gray</u>	<u>30</u>	<u>37</u>	<u>Limestone yellow brown (water)</u>	<u>37</u>	<u>44</u>	<u>Shale blue gray</u>	<u>44</u>	<u>51</u>	<u>Shale light gray</u>	<u>51</u>	<u>57</u>	<u>Shale Rusty Red</u>	<u>57</u>	<u>58</u>	7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
					From	To																																	
				<u>Top Soil</u>	<u>0</u>	<u>2</u>																																	
				<u>Clay brown</u>	<u>2</u>	<u>6</u>																																	
<u>Clay yellow</u>	<u>6</u>	<u>12</u>																																					
<u>Alluvium yellow gray (some water)</u>	<u>12</u>	<u>22</u>																																					
<u>Shale blue gray</u>	<u>22</u>	<u>30</u>																																					
<u>Shale light gray</u>	<u>30</u>	<u>37</u>																																					
<u>Limestone yellow brown (water)</u>	<u>37</u>	<u>44</u>																																					
<u>Shale blue gray</u>	<u>44</u>	<u>51</u>																																					
<u>Shale light gray</u>	<u>51</u>	<u>57</u>																																					
<u>Shale Rusty Red</u>	<u>57</u>	<u>58</u>																																					
8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																							
9. Casing: Material <u>PVC</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>36</u> in. RMP ☐ PVC ☒ Weight <u>15</u> lbs./ft. Dia. <u>8</u> in. to <u>58</u> ft. depth Wall Thickness: inches or Dia. <u>1/2</u> in. to <u>1</u> ft. depth gage No. <u>300</u>																																							
10. Screen: Manufacturer's name <u>Hand made</u> <u>The screen with saw</u> Type <u>PVC</u> Dia. <u>8"</u> Slot/gauze <u>1/4</u> Length <u>30'</u> Set between <u>28</u> ft. and <u>58</u> ft. Gravel pack? ☒ Size range of material <u>1/2 - 3/4</u>																																							
11. Static water level: <u>4</u> ft. below land surface Date <u>4-28-79</u>			12. Pumping level below land surfaces: <u>NA</u> <u>NA</u> ft. after <u>NA</u> hrs. pumping <u>NA</u> g.p.m. <u>NA</u> ft. after <u>NA</u> hrs. pumping <u>NA</u> g.p.m. Estimated maximum yield <u>NA</u> g.p.m.																																				
13. Water sample submitted: ☒ Yes ☐ No Date <u>4-28-79</u>			14. Well head completion: ☐ Pitless adapter <u>36</u> inches above grade																																				
15. Well grouted? <u>yes</u> With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>20</u> ft. to <u>0</u> ft.			16. Nearest source of possible contamination: <u>Creek</u> <u>100</u> ft. Direction <u>W</u> Type <u>NA</u> Well disinfected upon completion? ☒ Yes ☐ No																																				
17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Braddy Water Wells 363</u> Business name <u>R. S. Douglass KS</u> License No. _____ Address <u>Rose Hill KS</u> Signed <u>Richard Braddy</u> Date <u>4-28-79</u> Authorized representative																																				
18. Elevation:		19. Remarks:		20. Water well contractor's certification:																																			
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		<u>owner will install concrete slab and submit water sample</u>		(Use a second sheet if needed)																																			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5