

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>Butler</u>	Fraction <u>NW 1/4 SE 1/4 NW 1/4</u>	Section number <u>33</u>	Township number <u>T 28 S R 3 E/W</u>	Range number																		
2. Distance and direction from nearest town or city: <u>NE 1/4 N OR Rose Hill</u>			3. Owner of well: <u>Wayne Williams</u>																				
Street address of well location if in city: <u>2309 Dawn Hill</u>			R.R. or street: <u>535 N Oliver</u>																				
			City, state, zip code: <u>Wichita KS 67208</u>																				
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>8.5</u> in. Completion date <u>5-21-79</u>																			
				Well depth <u>46</u> ft.																			
				7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																			
5. Type and color of material		From To		8. Use: ☒ Domestic ☐ Public supply ☐ Industry																			
				☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																			
<table border="1" style="width:100%; border-collapse: collapse;"> <tr><td>clay brown</td><td>0</td><td>3</td></tr> <tr><td>clay yellow</td><td>3</td><td>7</td></tr> <tr><td>Limestone yellow (some water)</td><td>7</td><td>15</td></tr> <tr><td>shale gray green</td><td>15</td><td>25</td></tr> <tr><td>shale light gray</td><td>25</td><td>46</td></tr> <tr><td colspan="3">(water at 31')</td></tr> </table>		clay brown	0	3	clay yellow	3	7	Limestone yellow (some water)	7	15	shale gray green	15	25	shale light gray	25	46	(water at 31')					9. Casing: Material <u>PBS</u> Height: Above or below	
		clay brown	0	3																			
clay yellow	3	7																					
Limestone yellow (some water)	7	15																					
shale gray green	15	25																					
shale light gray	25	46																					
(water at 31')																							
Threated ☐ Welded <u>glue</u> Surface <u>14</u> in.																							
				RMP ☒ PVC ☐ Weight <u> </u> lbs./ft.																			
				Dia. <u>5</u> in. to <u>46</u> ft. depth Wall Thickness: inches or																			
				Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>200</u>																			
				10. Screen: Manufacturer's name <u>SUNFLOWER</u>																			
				Type <u>RMP</u> Dia. <u>5"</u>																			
				Slot/gauze <u>1/16</u> Length <u>10'</u>																			
				Set between <u>36</u> ft. and <u>46</u> ft.																			
				Gravel pack? <u>yes</u> Size range of material <u>1/4-3/4</u>																			
				11. Static water level: <u>12</u> ft. below land surface Date <u>5-22-79</u>																			
				12. Pumping level below land surfaces: <u>NA</u>																			
				<u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m.																			
				<u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m.																			
				Estimated maximum yield <u> </u> g.p.m.																			
				13. Water sample submitted: <u> </u> mo./day/yr.																			
				Yes ☒ No ☐ Date <u> </u>																			
				14. Well head completion: <u> </u>																			
				☒ Pitless adapter <u>14</u> inches above grade																			
				15. Well grouted? <u>yes</u>																			
				With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete																			
				Depth: From <u>13</u> ft. to <u>3</u> ft.																			
				16. Nearest source of possible contamination: <u>NA</u>																			
				ft. <u> </u> Direction <u> </u> Type <u> </u>																			
				Well disinfected upon completion? ☒ Yes ☐ No																			
				17. Pump: ☒ Not installed																			
				Manufacturer's name <u> </u>																			
				Model number <u> </u> HP <u> </u> Volts <u> </u>																			
				Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m.																			
				Type:																			
				☐ Submersible ☐ Turbine																			
				☐ Jet ☐ Reciprocating																			
				☐ Centrifugal ☐ Other																			
				18. Elevation:																			
19. Remarks: <u>owner will install concrete slab</u>		20. Water well contractor's certification:		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.																			
Topography: ☒ Hill ☒ Slope ☐ Upland ☐ Valley				Business name <u>Breddy water wells 363</u>																			
				Address <u>R 2 Douglass KS</u> License No. <u> </u>																			
				Signed <u>Richard Braddy</u> Date <u>5-22-79</u>																			
				Authorized representative																			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5