


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Butler</u> Fraction <u>NE 1/4 SW 1/4 NE 1/4</u> Section number <u>33</u> Township number <u>T 28 S</u> Range number <u>R 3 E</u>																																		
2. Distance and direction from nearest town or city: <u>1 1/2 E 1/2 N 1/4 E</u> Street address of well location if in city: <u>of Rose Hill KS.</u>																																		
3. Owner of well: <u>Don Hayden</u> R.R. or street: <u>100 E S. Knitter</u> City, state, zip code: <u>Rose Hill KS. 67133</u>																																		
4. Locate with "X" in section below: Sketch map: <u>Septic well x</u> <u>House drainage</u>																																		
																																		
5. Type and color of material																																		
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td><u>Top Soil</u></td> <td><u>0</u></td> <td><u>1</u></td> </tr> <tr> <td><u>Clay brown</u></td> <td><u>1</u></td> <td><u>3</u></td> </tr> <tr> <td><u>Limestone yellow</u></td> <td><u>3</u></td> <td><u>11</u></td> </tr> <tr> <td><u>Clay yellow green</u></td> <td><u>11</u></td> <td><u>25</u></td> </tr> <tr> <td><u>Clay light lavender</u></td> <td><u>25</u></td> <td><u>28</u></td> </tr> <tr> <td><u>Shale light gray</u></td> <td><u>28</u></td> <td><u>38</u></td> </tr> <tr> <td><u>Shale blue gray</u></td> <td><u>38</u></td> <td><u>50</u></td> </tr> <tr> <td><u>Shale gray (Hard)</u></td> <td><u>50</u></td> <td><u>78</u></td> </tr> <tr> <td><u>Shale gray green</u></td> <td><u>78</u></td> <td><u>85</u></td> </tr> <tr> <td colspan="3"><u>(water at 43')</u></td> </tr> </tbody> </table>			From	To	<u>Top Soil</u>	<u>0</u>	<u>1</u>	<u>Clay brown</u>	<u>1</u>	<u>3</u>	<u>Limestone yellow</u>	<u>3</u>	<u>11</u>	<u>Clay yellow green</u>	<u>11</u>	<u>25</u>	<u>Clay light lavender</u>	<u>25</u>	<u>28</u>	<u>Shale light gray</u>	<u>28</u>	<u>38</u>	<u>Shale blue gray</u>	<u>38</u>	<u>50</u>	<u>Shale gray (Hard)</u>	<u>50</u>	<u>78</u>	<u>Shale gray green</u>	<u>78</u>	<u>85</u>	<u>(water at 43')</u>		
	From	To																																
<u>Top Soil</u>	<u>0</u>	<u>1</u>																																
<u>Clay brown</u>	<u>1</u>	<u>3</u>																																
<u>Limestone yellow</u>	<u>3</u>	<u>11</u>																																
<u>Clay yellow green</u>	<u>11</u>	<u>25</u>																																
<u>Clay light lavender</u>	<u>25</u>	<u>28</u>																																
<u>Shale light gray</u>	<u>28</u>	<u>38</u>																																
<u>Shale blue gray</u>	<u>38</u>	<u>50</u>																																
<u>Shale gray (Hard)</u>	<u>50</u>	<u>78</u>																																
<u>Shale gray green</u>	<u>78</u>	<u>85</u>																																
<u>(water at 43')</u>																																		
6. Bore hole dia. <u>12</u> in. Completion date <u>11-27-78</u> Well depth <u>85</u> ft.																																		
7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																																		
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																		
9. Casing: Material <u>P15T</u> Height: Above or below Threaded ☐ Welded <u>glue</u> Surface <u>14</u> in. RMP ☒ PVC ☐ Weight <u> </u> lbs./ft. Dia. <u>5</u> in. to <u>85</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>200</u>																																		
10. Screen: Manufacturer's name <u>SUNFLOWER</u> <u>Mfg Inc</u> Type <u>RMP</u> Dia. <u>5"</u> Slot/gauze <u>1/16</u> Length <u>11 FT.</u> Set between <u>75</u> ft. and <u>85</u> ft. <u>45</u> ft. and <u>46</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/8 to 3/4</u>																																		
11. Static water level: <u>34</u> ft. below land surface Date <u>11-27-78</u> mo./day/yr.																																		
12. Pumping level below land surfaces: <u>NA</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.																																		
13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No ☐ Date <u> </u>																																		
14. Well head completion: <u>X</u> Pitless adapter <u>14"</u> Inches above grade																																		
15. Well grouted? <u>yes</u> With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete <u> </u> Depth: From <u>13</u> ft. to <u>3</u> ft.																																		
16. Nearest source of possible contamination: ft. <u>250'</u> Direction <u>W.</u> Type <u>septic</u> Well disinfected upon completion? ☒ Yes ☐ No																																		
17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																		
(Use a second sheet if needed)																																		
18. Elevation: Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley	19. Remarks: <u>owner will install concrete slab</u>																																	
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Brady Water Wells</u> <u>363</u> Business name License No. Address <u>R2 box #17A Douglas KS.</u> Signature <u>Richard Brady</u> Date <u>11-27-78</u> Authorized representative																																		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5