


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Butler	Fraction Lot 2 Abraham Add. NW 1/4 NW 1/4 NE 1/4	Section number 36	Township number T 28 S	Range number R 3E 6th E/W
2. Distance and direction from nearest town or city: 4 mi. east of Roashill, Ks. on 63rd st. Street address of well location if in city:			3. Owner of well: E. E. Rouse R.R. or street: 526 Allison City, state, zip code: Andover, Kansas 67002		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		
5. Type and color of material			From	To	
Soil			0	2	
Clay-red			2	12	
Lime			12	14	
Buff Shale			14	40	
Light Blue Shale			40	48	
Blue Shale			48	50	
White Shale-water			50	52	
Redbed			52	53	
Blue Shale			53	54	
White Shale			54	60	
White Lime			60	68	
White Shale			68	72	
Buff Lime			72	95	
Gray Shale			95	100	
(Use a second sheet if needed)					
18. Elevation: Topography: ☐ Hill ☒ Slope ☒ Upland ☐ Valley	19. Remarks: Mr. Rouse will make slab around casing.				
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Abraham & Plummer Business name Address Leon, Ks. 67074 License No. 181A Signed Jay Abraham Date 6-26-79 Authorized representative			6. Bore hole dia. 11 in. Completion date 6-14-79 Well depth 100 ft. 7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material Plas-X Weight: Above or below Threaded ☐ Welded ☐ Surface 14 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 8 in. to 100 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 322 10. Screen: Manufacturer's name Type Slots Dia. 8" Slot/gauze 1/8 Length 20' Set between 60-80 ft. and 80-100 ft. Gravel pack? ☒ Size range of material 5/8" 11. Static water level: 100 ft. below land surface Date 6-14-79 mo./day/yr. ☒ Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping 10 g.p.m. Estimated maximum yield ☐ g.p.m. 13. Water sample submitted: ☐ Yes ☒ No Date 14. Well head completion: Pitless adapter ☐ Inches above grade 15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 3 ft. to 14 ft. Pitless adapter. 16. Nearest source of possible contamination: ft. 1/2 Direction mi. SW Type area Well disinfected upon completion? ☒ Yes ☐ No 17. Pump: ☒ Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

Certain-teed 8" P.V.C. -1120-5 DR26-160 P.S.I. (ASTM D2241 NSF-PW)