

1 LOCATION OF WATER WELL:		Fraction		Form WWC-3		RSA 62a-1212			
County: Sedgwick		NE 1/4 NE 1/4 SW 1/4		Section Number 1		Township Number T 29 S		Range Number R 1	
Distance and direction from nearest town or city street address of well if located within city?									
83' North and 42' West of 1001 N. Buckner, Derby, Kansas									
52905002 MW-3									
2 WATER WELL OWNER: Kwik Shop, Inc.									
RR#, St. Address, Box #: 734 East 4th Street									
City, State, ZIP Code: Hutchinson, KS 67501									
Board of Agriculture, Division of Water Resources									
Application Number:									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:									
4 DEPTH OF COMPLETED WELL: 72.5 ft. ELEVATION: Approx. Surface Elev.: 1325 ft.									
WELL'S STATIC WATER LEVEL: 60.8 ft. below land surface measured on mo/day/yr 02/09/90									
Pump test data: Well water was ... ft. after ... hours pumping ... gpm									
Est. Yield: N/A gpm; Well water was ... ft. after ... hours pumping ... gpm									
Bore Hole Diameter: 6 in. to 72.5 ft. and ... in. to ... ft.									
WELL WATER TO BE USED AS:									
5 Public water supply 8 Air conditioning 11 Injection well									
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)									
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well									
Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted									
Water Well Disinfected? Yes No X									
5 TYPE OF BLANK CASING USED:									
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped									
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded									
7 Fiberglass Threaded X									
Blank casing diameter: 2 in. to 52 ft. Dia. in. to ... ft. Dia. in. to ... ft.									
Casing height above land surface: -4 in. weight ... lbs./ft. Wall thickness or gauge No. Schedule 40									
TYPE OF SCREEN OR PERFORATION MATERIAL:									
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement									
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)									
12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:									
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)									
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes									
7 Torch cut 10 Other (specify)									
SCREEN-PERFORATED INTERVALS: From 52 ft. to 72 ft. From ... ft. to ... ft.									
GRAVEL PACK INTERVALS: From 48.5 ft. to 72.5 ft. From ... ft. to ... ft.									
6 GROUT MATERIAL:									
1 Neat cement 2 Cement grout 3 Bentonite 4 Other									
Grout Intervals: From 0 ft. to 46.5 ft. From 46.5 ft. to 48.5 ft. From ... ft. to ... ft.									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)									
13 Insecticide storage									
Direction from well? Southeast How many feet? 75									
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0 0.5 Asphalt									
0.5 5.5 Brown Lean Clay									
5.5 20.5 Red-Brown Fat Clay									
20.5 50.0 Pale Red-Brown Lean to Fat Clay									
50.0 60.5 Pale Brown Sandy Lean Clay									
60.5 72.5 Light Brown Silty Sand									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 01/09/90 and this record is true to the best of my knowledge and belief. Kansas									
Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 01/09/90									
under the business name of Terracon Consultants, Inc. by (signature) [Signature]									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									