


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Sedgwick	Township name Salem	Fraction NW¹₄	Section number 1	Town number 29	Range number 1E
Distance and direction from nearest town or city:				3 Owner of well: Tom Mc Cawley Wichita, Kan.		
Street address of well location if in city: 5430 E. 72 St. S. Derby, Ks.				Address: Res. 149 N. Poplar Bus. 2628 E. 21st		
Locate with "X" in section below: N  W E S 1 Mile		Sketch map: abandon near foundation of house front → 26.5' new well-----→ X		4 Well depth: 80 ft. Date of completion 9-6-75 Well diameter 11 in.		
2 Type and color of material				5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				6 Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐		
				7 Casing: Material rmp Height above/below Threaded ☐ Welded ☐ Surface 12 in. Diam. 5 in. to 80 ft. depth Weight 200 lbs. Sked Drive shoe? ☐ Yes ☒ No		
				8 Screen: Manufacturer J&L Type RMP Dia. 5" Slot gauge .030 Length 10' Set between 50 ft. and 60 ft. 20&80' Fittings: Gravel pack ☒ Yes ☐ No Size range of material 3/8		
				9 Static water level: 55 ft. below land surface Date 9-6-75		
Note: Info Abandoned Well Back filled 80' old Galv. Cased Well to filled with-in 10' of top of Casing with clean Sand, Installed .0572 HTH with 5 Gal water at intervals while backfilling, Installed 10' Neat cement to Top of casing, Top of Casing is 30" B.G.L., Customer will complete backfill as he installs Submersible Pump.				10 Pumping level below land surface: 65 ft. after 1 hrs. Bail 8 g.p.m. ft. after 9 hrs. pumping 9 g.p.m. Estimated maximum yield 9 g.p.m.		
				11 Water sample submitted: ☐ Yes ☒ No Date 9-6-75		
				12 Well head completion: ☐ Pitless adapter 12 inches above grade		
				13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 10 ft. to 3 ft. B.G.L.		
				14 Nearest source of possible contamination: ft. 65 Direction N. Type Septic Well disinfected upon completion? ☒ Yes ☐ No		
(use a second sheet if needed)				15 Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				16 Remarks: elevation Aprox. 1360 MSL Owner of property Tom Mc Cawley installing Submersible Pump and will comply with State Health Dept. requirements Owner Tom Mc Cawley		
				Water well contractor's certification: 135 This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. B.C. Wilkinson Well Drilling 135A Business name _____ License No. _____ Address 1028 Ida, Wichita, Kan. Signed B.C. Wilkinson Date 9-14-75 Authorized representative		
				Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5