


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

Location of well:		County Sedgwick	Fraction NW NW 1/4 1/4 1/4	Section number 11	Township number T 29 S	Range number R 1E E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 8100 South Hillside Derby, Kansas			3. Owner of well: Joe Lee R.R. or street: 5228 Primrose City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: 			Sketch map:			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 8-23-78 Well depth 40 ft.	
Topsoil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Brown clay			2	9	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine sand			9	18	9. Casing: Material Styrene Height: Above or Below Before Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 40 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 200	
Coarse sand			18	26	10. Screen: Manufacturer's name Sunflower plastic Type styrene Dia. 5" Slot/size .06 Length 20' Set between 20 ft. and 40 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 1/4-1/8"	
Blue shale			26	40	11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 8-23-78	
					12. Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date ☐	
					14. Well head completion: capped ☐ Pitless adapter 12 inches above grade	
					15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 7 ft. to 17 ft.	
					16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type None Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks: Flat ground Well is to be in the basement. Septic system not installed at this time. No apparent source for contamination.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 10-3-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5