


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

NW SW NE NW

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Sedgwick	Township name Salem	Fraction NW 1/4	Section number 11	Town number 29	Range number 1E
Distance and direction from nearest town or city: 1-mi West of Derby Ks.			Owner of well: COMPLETE HOME Builders			
Street address of well location if in city: 8117 Millsap Drive			Address: P.O. Box 228 Mulvane, Kansas			
Locate with "X" in section below: 			Sketch map: Derby, Ks. Baltimore st			4 Well depth: 30 ft. Date of completion 4-19-75 Well diameter 11 in.
2 Type and color of material			From	To	5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
overburden			0	7	6 Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐	
fine sand			7	15	7 Casing: Material RMP Height (above) below Threaded ☐ Welded ☐ Surface 12 in. Diam. 200 lbs./ft. sked. 5 in. to 30 ft. depth Drive shoe? ☐ Yes ☒ No — in. to — ft. depth	
fine to med-coarse			15	25	8 Screen: Manufacturer J&L Type RMP Dia. 5" Slot/gauze .09375 Length 10 Set between 20 ft. and 30 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 3/8	
1/8-1/4" gravel			25	30	9 Static water level: 10 ft. below land surface Date 4-19-75	
Remarks: Test from 30-40' show dark disturbed soft shale with large inbed 1" gravel					10 Pumping level below land surfaces: 11 ft. after 1 hrs. pumping 43 g.p.m. — ft. after — hrs. pumping — g.p.m. Estimated maximum yield 150 g.p.m.	
					11 Water sample submitted: ☐ Yes ☒ No Date 4-19-75	
					12 Well head completion: ☐ Pitless adapter 12 casing inches above grade	
					13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 9 ft. to 3 ft. B.G.L.	
					14 Nearest source of possible contamination: ft. 50 Direction W Type Septic Well disinfected upon completion? ☒ Yes ☐ No	
					15 Pump: ☒ Not installed Manufacturer's name — Model number — HP — Volts — Length of drop pipe — ft. capacity — g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(use a second sheet if needed)						
16 Remarks: elevation G.L. Aprox 1275 Company(Home Builders)Plumbers will install Sub. Pump & associated Equipment, Test water & ect. Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			17 Water well contractor's certification: 135A This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Wilkinson Well Drilling 135 Business name 1028 Ida, Wichita, Ks. License No. — Address — Signed B. C. Wilkinson Date 4-19-75 Authorized representative			

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5