


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 SE 1/4 SW 1/4	Section number 19	Township number T 29 S	Range number R 1E E/W
2. Distance and direction from nearest town or city: 1/4 East and 1/4 North of Clearwater Road and Meridian. Clearwater, Kansas			3. Owner of well: Garland Bell R.R. or street: Peck, Kansas City, state, zip code:		
4. Locate with "X" in section below: Sketch map: Peck, Kansas			6. Bore hole dia. 30 in. Completion date 5-3-77 Well depth 75 ft.		
			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
5. Type and color of material			From	To	9. Casing: Material Transite Height: Above or below See #19 12 in. Threaded ☐ Welded ☐ Surface ☐ in. RMP ☐ PVC ☐ Weight 37 lbs./ft. Dia. 16 in. to 75 ft. depth; Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth; gage No. 3/4
Clay			0	12	10. Screen: Manufacturer's name Johnson Type Irrigator Dia. 16" Slot/gauge .100 Length 15' Set between 45 ft. and 55 ft. 70 ft. and 75 ft. Gravel pack yes Size range of material 1/2-1/8"
Sandy Clay			12	25	11. Static water level: 29 ft. below land surface Date 5-3-77
Medium to Coarse Sand & Gravel			25	56	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
Clay			56	58	13. Water sample submitted: ____ mo./day/yr. ☐ Yes ☐ No Date ____
Fine to Coarse Sand			58	75	14. Well head completion: 12 inches above grade ☐ Pitless adapter to 2 fine sand mix.
					15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: NONE ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: Not installed Manufacturer's name valley Model number 10MHE-8 HP 80 Volts 460 Length of drop pipe 60 ft. capacity 600 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: Flat Ground From #9 Banded But Joint No apparent source for contamination.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. ____ Address 321 Orville Signed Garland Bell Date 5-6-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5