

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

*Jo BWS
4-21-80*

1. Location of well:	County Sedgwick	Fraction SW 1/4 SW 1/4 SW 1/4	Section number 36	Township number T 29 S	Range number R 1 E				
2. Distance and direction from nearest town or city: 1 mile west of Mulvane Street address of well location if in city:			3. Owner of well: City of Mulvane R.R. or street: Mulvane, Kansas 67110 City, state, zip code:						
4. Locate with "X" in section below: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile Sketch map: Well No. 4			NW	NE	SW	SE	6. Bore hole dia. 38 in. Completion date Well depth 53 ft. 4/15/80		
NW	NE								
SW	SE								
			7. ☐ Cable tool ☐ Rotary ☐ Driven ☒ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary						
			8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other						
			9. Casing: Material Steel Height: Above ground Threaded ☐ Welded ☒ Surface 36 in. RMP ☐ PVC ☐ Weight 43.77 lbs./ft. Dia. 12 in. to 46 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 1330						
5. Type and color of material			From	To					
Top soil			0	2	10. Screens: Manufacturer's name Mustang				
Sandy clay			2	12	Type S.S. Wire Wr Dia. 12"				
Fine sand			12	20	Slot/gauze 50 Length 10'				
Med. sand & gravel			20	53	Set between 43 ft. and 53 ft. ft. and 53 ft.				
Blue clay & shale			53	55	Gravel pack? yes Size range of material 1/8x1/2				
					11. Static water level: 8 ft. below land surface Date 4/15/80				
					12. Pumping level below land surfaces: 4 ft. after 4 hrs. pumping 600 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1000 g.p.m.				
					13. Water sample submitted: ☐ Yes ☒ No Date ☐				
					14. Well head completion: ☐ Pitless adapter 36 inches above grade				
					15. Well grouted? yes 0-18 18-20 With: ☐ Neat cement ☒ Bentonite ☒ Concrete Depth: From 0 ft. to 20 ft.				
					16. Nearest source of possible contamination: Farm ft. 1500 Direction North Type House Well disinfected upon completion? ☒ Yes ☐ No				
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other				
			(Use a second sheet if needed)						
18. Elevation:		19. Remarks:							
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley									
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. ☐ Address ☐ Date 4/14/80 Signed <i>[Signature]</i> Authorized representative									

Forward the white, blue and pink copies to the Department of Health and Environment

Farm WWC-5