

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL:		Fraction		Section Number	Township Number	Range Number																																										
County: Sedgwick		NW ¼ NW ¼ NW ¼		8	T 29 S	R 2 E																																										
Distance and direction from nearest town or city street address of well if located within city? 400 N. Rock Road, Derby KS				Global Positioning System (decimal degrees, min. of 4 digits)																																												
2 WATER WELL OWNER: Casey's General Store RR#, St. Address, Box # : PO Box 3001 City, State, ZIP Code : Ankeny IA 50021-3001				Latitude: N 37.54753°																																												
				Longitude: W 97.24381°																																												
				Elevation: RIM: 1290.64; TOC: 1290.39																																												
				Datum: WGS84																																												
Data Collection Method: legal survey																																																
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 30.2 ft.																																														
N <table border="1" style="margin: auto;"> <tr><td>X</td><td></td></tr> <tr><td>NW</td><td>NE</td></tr> <tr><td>SW</td><td>SE</td></tr> </table> S W E		X		NW	NE	SW	SE	5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) ② PVC 4 ABS 7 Fiberglass Blank casing diameter 2 in. to 15.2 ft., Dia in. to ft., Dia in. to ft. Casing height below land surface 0.25 ft., Weight lbs./ft. Wall thickness or gauge No.																																								
		X																																														
		NW	NE																																													
		SW	SE																																													
CASING JOINTS: Glued Clamped Welded Threaded X																																																
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass ⑦ PVC 9 ABS 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole)																																																
SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot ③ Mill slot 5 Gauze wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw Cut 10 Other (specify)																																																
SCREEN-PERFORATED INTERVALS: From 15.2 ft. to 30.2 ft. From ft. to ft. From ft. to ft. From ft. to ft. GRAVEL PACK INTERVALS: From 13 ft. to 30.4 ft. From ft. to ft. From ft. to ft. From ft. to ft.																																																
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ③ Bentonite ④ Other Concrete: 0-1ft Grout Intervals From 1 ft. to 13 ft. From ft. to ft. From ft. to ft.																																																
What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage 16 Other (specify below) 2 Sewer lines 5 Cess pool 8 Sewage lagoon ⑪ Fuel storage 14 Abandoned water well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 15 Oil well/ gas well Direction from well? E How many feet? ~20ft																																																
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0.5</td> <td>Concrete</td> <td></td> <td></td> <td></td> </tr> <tr> <td>0.5</td> <td>5</td> <td>Brown silty clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>5</td> <td>10</td> <td>Brown sandy clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>10</td> <td>20</td> <td>Brown medium grained sandy clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td>30.4</td> <td>Tan medium grained sand w/ a 3" layer of clay at 23 ft</td> <td></td> <td></td> <td></td> </tr> <tr> <td colspan="6" style="text-align: center;">Flushmount waiver from BOW</td> </tr> </tbody> </table>							FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	0.5	Concrete				0.5	5	Brown silty clay				5	10	Brown sandy clay				10	20	Brown medium grained sandy clay				20	30.4	Tan medium grained sand w/ a 3" layer of clay at 23 ft				Flushmount waiver from BOW					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																											
0	0.5	Concrete																																														
0.5	5	Brown silty clay																																														
5	10	Brown sandy clay																																														
10	20	Brown medium grained sandy clay																																														
20	30.4	Tan medium grained sand w/ a 3" layer of clay at 23 ft																																														
Flushmount waiver from BOW																																																
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, ② reconstructed, or ③ plugged under my jurisdiction and was completed on (mo/day/year) 7/17/12 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 757 This Water Well Record was completed on (mo/day/year) 9/4/12 under the business name of Larsen & Associates, Inc. by (signature) <i>[Signature]</i>																																																
INSTRUCTIONS: Please fill in blanks or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell .																																																

White