

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		NW 1/4 NW 1/4 NE 1/4	4	T 29 S	R 2 E
Distance and direction from nearest town or city street address of well if located within city? From the NE corner of Sec. 4, T29S, R2E, 2640' West, 589' South, 245' East.					
2 WATER WELL OWNER: Jim Inkelaar					
RR#, St. Address, Box # : 7300 South 103 East			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Derby, Ks. 67037			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 57 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 27 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 1.0 ft. below land surface measured on mo/day/yr 6/29/92			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 1.4 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 10 in. to 57 ft. and in. to ft.			
WELL WATER TO BE USED AS:		5 Public water supply 8 Air conditioning 11 Injection well ☒ 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted		Water Well Disinfected? Yes ☒ No			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile		CASING JOINTS: Glued ☒ Clamped	
☒ 2 PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)		Welded	
		7 Fiberglass		Threaded	
Blank casing diameter 6 in. to 24 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 36 in., weight lbs./ft. Wall thickness or gauge No. 160					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass		☒ 7 PVC 8 RMP (SR)		10 Asbestos-cement	
2 Brass 4 Galvanized steel 6 Concrete tile		9 ABS		11 Other (specify)	
				12 None used (open hole)	
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped		☒ 8 Saw cut 11 None (open hole)			
2 Louvered shutter 4 Key punched 6 Wire wrapped		9 Drilled holes			
		10 Other (specify)			
SCREEN-PERFORATED INTERVALS: From 57 ft. to 24 ft., From ft. to ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 57 ft. to 23 ft., From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL:					
☒ 1 Neat cement 2 Cement grout 3 Bentonite 4 Other		☒ Neat Cement			
Grout intervals: From 23 ft. to 12 ft., From 12 ft. to 6 ft., From 6 ft. to 2 ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy		10 Livestock pens 14 Abandoned water well			
2 Sewer lines 5 Cess pool 8 Sewage lagoon		11 Fuel storage 15 Oil well/Gas well			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		12 Fertilizer storage 16 Other (specify below)			
		13 Insecticide storage			
Direction from well? SE		How many feet? 182			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	Top Soil			
4	33	Yellow gray shale with thin Gypsum stringers			
33	47	Blue gray shale with thin limestone			
47	53.5	Yellow gray shale			
53.5	56	Gypsum			
56	57	Blue gray shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ (1) constructed, ☐ (2) reconstructed, or ☐ (3) plugged under my jurisdiction and was completed on (mo/day/year) 6/20/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 279 This Water Well Record was completed on (mo/day/yr) 6/29/92 under the business name of Fudge Drilling by (signature) <i>Muhm R. Fudge</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					