

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 NW 1/4 NE 1/4	Section number 20	Township number T 29 S	Range number R 2E E/W
2. Distance and direction from nearest town or city: 9117 East 95th South, then 1/4 mile South Street address of well location if in city: in pasture. Derby, Kansas		3. Owner of well: Ray Warren R.R. or street: P.O. Box 86 City, state, zip code: Derby, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile Sketch map:		6. Bore hole dia. 11 in. Completion date Well depth 80 ft. 10-19-78 7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 80 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 200			
5. Type and color of material		From	To	10. Screen: Manufacturer's name Sunflower plastic Type styrene Dia. 5" Slot/gauge 1/16 .06 Length 30' Set between 50 ft. and 80 ft. ft. and ☐ ft. Gravel pack? ☒ yes Size range of material 1/4-1/8"	
Topsoil		0	3	11. Static water level: ☐ mo./day/yr. 20 ft. below land surface Date 10-19-78	
Brown clay		3	16	12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
Light tan clay		16	36	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date ☐	
Light tan clay mixed with fine sand		36	50	14. Well head completion: ☐ Pitless adapter 12 capped Inches above grade	
Medium sand		50	57	15. Well grouted? ☒ yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
Blue shale		57	80	16. Nearest source of possible contamination: ft. 15 Direction S.E. Type Septic Well disinfected upon completion? ☒ Yes tank No	
				17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. 67209 Address 10-25-78 Signed M. Arnold Date 10-25-78 Authorized representative	
18. Elevation:		19. Remarks:			
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5