

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Butler		SW 1/4 NW 1/4 SW 1/4	23	T 29 S	R 4 W
Distance and direction from nearest town or city street address of well if located within city?					
2 WATER WELL OWNER: L. Dee McFaddin					
RR#, St. Address, Box # : Rt 3 Box 63			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Douglas, Ks. 67039			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 65 ft. ELEVATION: _____ ft.			
		Depth(s) Groundwater Encountered 1. 40 ft. 2. _____ ft. 3. _____ ft.			
		WELL'S STATIC WATER LEVEL 32 1/2 ft. below land surface measured on mo/day/yr 8/6/88			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield 11 gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter 10 in. to _____ ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? Yes ☒ No _____			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ☒ Clamped _____
☒ PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded _____
			7 Fiberglass		Threaded _____
Blank casing diameter 5 in. to 32 1/2 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.					
Casing height above land surface 18 in., weight 160 lbs./ft. Wall thickness or gauge No. _____					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	☒ PVC	10 Asbestos-cement
2 Brass		4 Galvanized steel	6 Concrete tile	8 RMP (SR)	11 Other (specify) _____
				9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	☒ Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify) _____	
SCREEN-PERFORATED INTERVALS: From 32 1/2 ft. to 65 ft., From _____ ft. to _____ ft.					
From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From 30 ft. to 65 ft., From 30 ft. to _____ ft.					
From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: ☒ Neat cement 2 Cement grout ☒ Bentonite 4 Other _____					
Grout Intervals: From 23 ft. to 3 ft., From 30 ft. to 23 ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
☒ Septic tank		4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
				13 Insecticide storage	
Direction from well? S		How many feet? 100			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
1	4	Top Soil grading down to red brown shale			
4	20	Red brown to red shale with thin bands of green shale			
20	26	Yellow gray shale			
26	26.8	Limestone with chert			
26.8	28	Yellow gray shale			
28	33	Limestone			
33	40	Blue gray clay			
40	42	Hard blue gray fissal shale			
42	65	Blue gray shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8/6/88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 279 This Water Well Record was completed on (mo/day/yr) 8/6/88 under the business name of Fudge Drilling by (signature) <i>Michin R. Fudge</i>					