

Sent to Leonard 5-16-77

USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Butler</u>		Fraction <u>SE 1/4 NW 1/4 NW 1/4</u>		Section number <u>28</u>		Township number <u>T 29 S R 4</u>		Range number <u>EW</u>	
2. Distance and direction from nearest town or city: <u>1/2 S</u>				3. Owner of well: <u>City of Douglass</u>					
Street address of well location if in city: <u>Douglass</u>				R.R. or street: <u>Douglass Kans</u>					
4. Locate with "X" in section below:				Sketch map:		6. Bore hole dia. <u>12</u> in. Completion date <u>4-19-76</u>			
						Well depth <u>150</u> ft.			
						7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
						8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
						9. Casing: Material <u>gal</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>36</u> in. RMP ☐ PVC ☒ Weight <u>5.5</u> lbs./ft. Dia. <u>8</u> in. to <u>50</u> ft. depth Wall Thickness: inches or Dia. <u>8</u> in. to <u>50</u> ft. depth gage No. <u>332</u>			
5. Type and color of material				From		To		10. Screen: Manufacturer's name <u>Central Service</u>	
<u>yellow lime</u>				<u>0</u>		<u>17</u>		<u>McPherson Transline</u>	
<u>Blue shale</u>				<u>17</u>		<u>23</u>		Type <u>PVC</u> Dia. <u>8 in</u>	
<u>grey shale</u>				<u>23</u>		<u>35</u>		Slot/gauze _____ Length _____	
<u>yellow shale</u>				<u>35</u>		<u>57</u>		Set between _____ ft. and _____ ft.	
<u>water</u>				<u>57</u>				Gravel pack? <u>no</u> Size range of material _____	
<u>grey lime</u>				<u>57</u>		<u>65</u>		11. Static water level: _____ mo./day/yr.	
<u>Blue shale</u>				<u>65</u>		<u>70</u>		<u>33</u> ft. below land surface Date <u>4-19-76</u>	
<u>grey lime</u>				<u>70</u>		<u>74</u>		12. Pumping level below land surfaces:	
<u>Blue shale</u>				<u>74</u>		<u>76</u>		<u>43</u> ft. after <u>146</u> hrs. pumping <u>41.5</u> g.p.m.	
<u>grey lime</u>				<u>76</u>		<u>82</u>		_____ ft. after _____ hrs. pumping _____ g.p.m.	
<u>Red shale</u>				<u>82</u>		<u>85</u>		Estimated maximum yield <u>41.5</u> g.p.m.	
<u>grey lime</u>				<u>85</u>		<u>140</u>		13. Water sample submitted: _____ mo./day/yr.	
<u>Brown lime</u>				<u>140</u>		<u>150</u>		Yes ☒ No ☐ Date _____	
								14. Well head completion:	
								_____ Pitless adapter <u>36</u> Inches above grade	
								15. Well grouted? <u>yes</u>	
								With: ☒ Neat cement ☐ Bentonite ☐ Concrete	
								Depth: From <u>34</u> ft. to <u>10</u> ft.	
								16. Nearest source of possible contamination: <u>small</u>	
								ft. <u>150</u> Direction <u>NW</u> Type <u>Pond</u>	
								Well disinfected upon completion? Yes ☒ No ☐	
								17. Pump: _____ Not installed	
								Manufacturer's name <u>Howells</u>	
								Model number <u>UD67JM32</u> HP <u>5</u> Volts <u>230</u>	
								Length of drop pipe <u>130</u> ft. capacity _____ g.p.m.	
								Type:	
								☒ Submersible ☐ Turbine	
								☐ Jet ☐ Reciprocating	
								☐ Centrifugal ☐ Other	
18. Elevation:				19. Remarks:		20. Water well contractor's certification:			
Topography:						This well was drilled under my jurisdiction and this report			
☐ Hill						is true to the best of my knowledge and belief.			
☒ Slope						<u>Wike well drilling</u> <u>122</u>			
☐ Upland						Business name _____ License No. _____			
☐ Valley						Address <u>Augusta Kans</u>			
						Signed <u>Wm Wike</u>			
						Authorized representative <u>4-19-76</u>			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5