

1 LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number		
County: <u>Butler</u>		<u>NW 1/4 NW 1/4 NE 1/4</u>	<u>26</u>	<u>T 29 S</u>	<u>R 5 E</u>		
Distance and direction from nearest town or city? <u>2.50 1 1/2 E of</u>			Street address of well if located within city?				
2 WATER WELL OWNER: <u>Smileyville Santa Laura Inc.</u>							
RR#, St. Address, Box # : <u>R #2</u>			Board of Agriculture, Division of Water Resources				
City, State, ZIP Code : <u>Douglas KS 67039</u>			Application Number:				
3 DEPTH OF COMPLETED WELL <u>110</u> ft. Bore Hole Diameter <u>12</u> in. to <u>110</u> ft., and <u>110</u> in. to <u>110</u> ft.							
Well Water to be used as:							
☒ Domestic ☐ Irrigation ☐ Feedlot ☐ Industrial		☐ Public water supply ☐ Oil field water supply ☐ Lawn and garden only		☐ Air conditioning ☐ Dewatering ☐ Observation well ☐ Injection well ☐ Other (Specify below)			
Well's static water level <u>33</u> ft. below land surface measured on <u>12</u> month <u>8</u> day <u>79</u> year							
Pump Test Data <u>NA</u> : Well water was <u>NA</u> ft. after <u>NA</u> hours pumping <u>NA</u> gpm							
Est. Yield <u>NA</u> gpm: Well water was <u>NA</u> ft. after <u>NA</u> hours pumping <u>NA</u> gpm							
4 TYPE OF BLANK CASING USED:							
☐ Steel ☒ PVC ☐ RMP (SR) ☐ ABS		☐ Wrought iron ☐ Asbestos-Cement ☐ Fiberglass		☐ Concrete tile ☐ Other (specify below) Casing Joints: Glued ☒ Clamped ☐ Welded ☐ Threaded ☐			
Blank casing dia <u>5</u> in. to <u>90</u> ft. Dia <u>5</u> in. to <u>90</u> ft. Dia <u>5</u> in. to <u>90</u> ft. Dia <u>5</u> in. to <u>90</u> ft.							
Casing height above land surface <u>12</u> in., weight <u>14</u> lbs./ft. Wall thickness or gauge No <u>14</u>							
TYPE OF SCREEN OR PERFORATION MATERIAL:							
☐ Steel ☐ Brass ☐ Stainless steel ☐ Galvanized steel		☐ Fiberglass ☐ Concrete tile ☐ Gauzed wrapped ☐ Wire wrapped ☐ Torch cut		☒ PVC ☐ Asbestos-cement ☐ Other (specify) ☐ None used (open hole)			
Screen or Perforation Openings Are:							
☐ Continuous slot ☐ Louvered shutter		☐ Mill slot ☐ Key punched		☒ Saw cut ☐ Drilled holes ☐ Other (specify)			
Screen-Perforation Dia <u>5</u> in. to <u>110</u> ft. Dia <u>5</u> in. to <u>110</u> ft. Dia <u>5</u> in. to <u>110</u> ft. Dia <u>5</u> in. to <u>110</u> ft.							
Screen-Perforated Intervals: From <u>90</u> ft. to <u>110</u> ft. From <u>90</u> ft. to <u>110</u> ft. From <u>90</u> ft. to <u>110</u> ft. From <u>90</u> ft. to <u>110</u> ft.							
Gravel Pack Intervals: From <u>110</u> ft. to <u>14</u> ft. From <u>110</u> ft. to <u>14</u> ft. From <u>110</u> ft. to <u>14</u> ft. From <u>110</u> ft. to <u>14</u> ft.							
5 GROUT MATERIAL:							
☐ Neat cement ☒ Cement grout		☐ Bentonite ☐ Other					
Grouted Intervals: From <u>14</u> ft. to <u>4</u> ft. From <u>14</u> ft. to <u>4</u> ft. From <u>14</u> ft. to <u>4</u> ft. From <u>14</u> ft. to <u>4</u> ft.							
What is the nearest source of possible contamination:							
☒ Septic tank ☐ Sewer lines ☐ Lateral lines		☐ Cess pool ☐ Seepage pit ☐ Pit privy		☐ Sewage lagoon ☐ Feed yard ☐ Livestock pens			
Direction from well <u>E</u> How many feet <u>90</u> ? Water Well Disinfected? Yes ☒ No ☐							
Was a chemical/bacteriological sample submitted to Department? Yes ☐ No ☒ If yes, date sample was submitted <u>NA</u> month <u>NA</u> day <u>NA</u> year							
If Yes: Pump Manufacturer's name <u>Valley</u> Model No. <u>S1208-MF-352</u> Volts <u>230</u>							
Depth of Pump Intake <u>105</u> ft. Pumps Capacity rated at <u>12</u> gal./min.							
Type of pump: ☒ Submersible ☐ Turbine ☐ Jet ☐ Centrifugal ☐ Reciprocating ☐ Other							
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on <u>12</u> month <u>8</u> day <u>79</u> year							
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>362</u>							
This Water Well Record was completed on <u>12</u> month <u>17</u> day <u>79</u> year under the business name of <u>Brady Water Wells</u> by (signature) <u>Richard Brady</u>							
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		0	1	Top Soil			
		1	17	clay, Red			
		17	20	clay & gravel yellow			
		20	29	limestone yellow			
		29	88	shale blue gray			
		88	96	chert gray			
		96	110	shale gray/green			
ELEVATION: <u>Slope</u>							
Depth(s) Groundwater Encountered 1. <u>29</u> ft. 2. <u>88</u> ft. 3. <u>NA</u> ft. 4. <u>NA</u> ft. (Use a second sheet if needed)							

OFFICE USE ONLY

T

29

R

5

DEN

SEC.

26

NW 1/4

NW 1/4

NE 1/4

1/4