

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

NE NW SW

1. Location of well:		County Doniphan	Fraction NW 1/4 SE 1/4 NW 1/4	Section number 25	Township number T 2	Range number S R 19	<input checked="" type="checkbox"/> EW
2. Distance and direction from nearest town or city: 1 mile south of Highland, Kansas Street address of well location if in city:			3. Owner of well: Leonard Blevins R.R. or street: R R 1 City, state, zip code: Highland, Ks. 66035				
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. <u>36</u> in. Completion date <u>5-5-82</u> Well depth <u>59</u> ft. bore hole <u>1 1/4"</u> to <u>11"</u>		
		<p style="text-align: center;">HOUSE</p> <p style="text-align: center;">DRAINAGE PASTURE</p> <p style="text-align: center;">WELL ← 1000'</p>			7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input checked="" type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
					8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
5. Type and color of material				From	To	9. Casing: Material <u>Concrete</u> Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>30</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>200</u> lbs./ft. Dia. <u>30</u> in. to <u>59</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gage No. <u>2"</u>	
light brown windblown				0	8	10. Screen: Manufacturer's name _____ Type <u>NO SCREEN</u> Dia. _____ Slot/gauze _____ Length _____ Set between _____ ft. and _____ ft. _____ ft. and _____ ft. Gravel pack? _____ Size range of material _____	
same - with small pieces of chalk				8	12	11. Static water level: _____ mg./day/yr. <u>35</u> ft. below land surface Date <u>5-4-82</u>	
hard yellow clay				12	19	12. Pumping level below land surfaces: <u>37</u> ft. after <u>2</u> hrs. pumping <u>15</u> g.p.m. <u>39</u> ft. after <u>3</u> hrs. pumping <u>15</u> g.p.m. Estimated maximum yield <u>13</u> g.p.m.	
very hard yellow clay				19	35	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
water bearing brown sand gradually turning to				35	59	14. Well head completion: <input type="checkbox"/> Pitless adapter _____ Inches above grade	
gravel near 50 feet and large baseball size						15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>11</u> ft.	
gravel between 50 and 59 feet.						16. Nearest source of possible contamination: ft. <u>1,000</u> Direction <u>NE</u> Type <u>feedlot</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Very productive						17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)							
18. Elevation: <u>1060</u>		19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
Topography: <input checked="" type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley					Popplewell Well Boring 320 Business name _____ License No. _____ Address <u>Amity, Mo. 64122</u> Signed <u>Larry Popplewell</u> Date <u>May 25 1982</u> Authorized representative		