

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <i>Washington</i>	Fracture <i>NE 1/4 SE 1/4 NW 1/4</i>	Section number <i>6</i>	Township number <i>T 2 S R 3 E W</i>	Range number <i>3</i>
2. Distance and direction from nearest town or city: <i>1/4 E 1/4 S</i>		3. Owner of well: <i>Justin & Mable Gordon</i>			
Street address of well location if in city: <i>Road South of Church</i>		R.R. or street: <i>R.R. # 1 Box 9</i>			
		City, state, zip code: <i>Morrowville, Kans. 66958</i>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <i>8</i> in. Completion date: <i>10-31-78</i> Well depth <i>182</i> ft.	
N		Sketch map: <i>Morrowville</i>		7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
W				8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
S				<input checked="" type="checkbox"/> Casing: Material <i>PVC</i> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <i>12</i> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <i>200</i> lbs./ft. Dia. <i>5</i> in. to <i>182</i> ft. depth <input checked="" type="checkbox"/> Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <i>200</i>	
5. Type and color of material			From	To	10. Screen: Manufacturer's name <i>Plastic</i> <i>N.S.F. approved 200</i> Type <i>Plastic</i> Dia. <input type="checkbox"/> Slot/gauze <i>3.5</i> Length <i>20</i> Set between <i>162</i> ft. and <i>182</i> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <i>well gravel</i>
<i>Soil Top</i>			<i>0</i>	<i>2</i>	11. Static water level: <i>115</i> ft. below land surface Date <i>10-31-78</i> mo./day/yr.
<i>clay Brown</i>			<i>2</i>	<i>12</i>	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
<i>clay Tan</i>			<i>12</i>	<i>18</i>	13. Water sample submitted: ____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ____
<i>clay Sandy</i>			<i>18</i>	<i>24</i>	14. Well head completion: <i>capped</i> <input type="checkbox"/> Pitless adapter ____ inches above grade
<i>clay Red & Gray</i>			<i>24</i>	<i>28</i>	15. Well grouted? <i>Yes</i> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <i>0</i> ft. to <i>20</i> ft.
<i>clay Gray</i>			<i>28</i>	<i>47</i>	16. Nearest source of possible contamination: ft. <i>100</i> Direction <i>E</i> Type <i>Coals</i> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
<i>clay fire</i>			<i>47</i>	<i>58</i>	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name ____ Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
<i>clay Tan</i>			<i>58</i>	<i>66</i>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Blue Valley Drilling 234D</i> Business name <i>Blue Rapids, Mo 66411</i> License No. ____ Address <i>Gerold Strader</i> Date <i>11-5-78</i> Signed <i>Gerold Strader</i> Authorized representative
<i>clay fire</i>			<i>66</i>	<i>77</i>	
<i>Rock sand Hard</i>			<i>77</i>	<i>79 1/2</i>	
<i>clay fire</i>			<i>79 1/2</i>	<i>164</i>	
<i>Rock sand</i>			<i>164</i>	<i>182</i>	
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification:		
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley					

T
R
W
Sec
 2
3
W
 1/4
1/4
1/4
1/4
 NE
SE
NW