

CRAWFORD 10

184 ROSE MARTIN CO TULSA T. OKLAHOMA

31-30-22E

WELL RECORD

PROPERTY OF DONALD P. OAK
Record of Well No. Water Supply Well (Housewart) Farm
Location 2561' north and 151' east of SW corner Sec. 31 T30S R22E
C NW NW NW SW - DRH-KGS

Sec. 31 Twp. 30 Range. 22 County. Crawford State
Rig Commenced Rig Completed
Rig Contractor
Drilling Commenced Drilling Completed 01-01-1954
Contractor Oak Drilling Company Price per foot \$

CASING AND TUBING RECORD

Table with 6 columns: SIZE, FEET, MAKE, SIZE, FEET, MAKE. Contains data for Conductor (20 in, 15 1/2 in, 12 in, 10 in), 8 1/4 in, and 6 1/2 in tubing.

Water Well ft. depth, Casing ft.

Table with columns: NAME OF SANDS, TOP, BOTTOM, FEET OF SAND, INITIAL TORPEDO (Quarts, Date of Shot). Includes a Total Depth row.

Record of Sand and Oil Showing

How Tubed, Plugged

Production first 24 hours

Details of shot

County Recorded

Sec. Twp. R

Large table with columns: DATE CLEANED OUT, TORPEDOED (Quarts, Date Re-Shot). Contains multiple empty rows for data entry.

Reference corner

THICKNESS  
OF STRATA

FORMATION

DEPTH

*House near Water Supply Well  
31-30-08E  
Donald P. Dak*

THICKNESS OF STRATA	FORMATION	DEPTH	Notes
32	Soil	32	
17	Lime	49	
5	Shale	54	
15	Lime	69	
6	Shale black	75	6 bailers water per hr.
100	Shale light	175	
10	Lime shells	185	
15	Shale dark	200	
15	Shale light	215	
1	Lime	216	
18-	Shale light	234	
15	Oil sand broken	249	S.L.M. 236' Good show of oil 236'
10	Shale dark	259	
21	Shale light	280	
10	Shale dark	290	
40	Shale light	330	
15	Sand light	345	Tucker sand
25	Shale light	370	
10	Shale dark	380	
45	Shale light	425	
35	Shale dark	460	
35	Shale black	495	
7	Part of iron	502	
6	Chat	508	
32	Lime	540	S.L.M. 620'. Run 620' 4 7/8" csg
10	Lime brown & sandy	550	run 114 sacks of cement.
18	Brown lime & w flint	568	
52	Grey lime & W flint	620	
20	Grey lime	640	Very hard, cut bits had 3 to 5 ft. out of bit. Little water 7 bailers per hr. @ 644'
4	Gray lime	644	
4	Gray lime	648	Hit soft spot @ 647', drilled about 9" in less than 5 minutes. Brought tools out 5:30 had approx 225' water in hole.
62	Gray lime	710	
10	Gray lime & w Flint	720	
112	Gray lime	832	
19	Green shall	851	More water from 863 to 868'. Hole filled to 180' of top. Pailed 1 hr. could not lower it. No smell, a little salty.
61	Grey Lime	912	