

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well: County <b>Cowley</b> Fraction <b>SE 1/4 SE 1/4 NE 1/4</b> Section number <b>15</b> Township number <b>T 30 S R 3</b> Range number <b>E 1/4</b>	
2. Distance and direction from nearest town or city: <b>3 miles West of Rock Ks.</b> Street address of well location if in city:	
3. Owner of well: <b>MARVIN ROE</b> R.R. or street: <b>R2 Box 47</b> City, state, zip code: <b>Udall KS 67146</b>	
4. Locate with "X" in section below: <div style="display: flex; align-items: center;"> <div style="margin-right: 20px;"> </div> <div> <p>Sketch map:</p> </div> </div>	
5. Type and color of material	
	From To
Top Soil	0 1
clay Red	1 4
clay yellow	4 5
limestone yellow	5 33
clay gray	33 37
Shale blue gray	37 45
clay green	45 50
clay lavender	50 59
Shale gray	59 62
(water at 22 to 33 ft)	
6. Bore hole dia. <b>8.5</b> in. Completion date <b>11-7-78</b> Well depth <b>62</b> ft.	
7. <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
9. Casing: Material <b>PBS</b> Height <b>72</b> or below Threading <b>glue</b> Surface <b>72</b> in. RMP <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>5</b> in. to <b>62</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>200</b>	
10. Screen: Manufacturer's name <b>SUNFLOWER MFG. INC.</b> Type <b>RMP</b> Dia. <b>5 1/4</b> Slot/gauze <b>1/16</b> Length <b>10'</b> Set between <b>52</b> ft. and <b>62</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/8 to 1/4</b>	
11. Static water level: <b>22 ft.</b> below land surface Date <b>11-7-78</b> mo./day/yr.	
12. Pumping level below land surfaces: <b>NA</b> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.	
13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <input type="checkbox"/> mo./day/yr.	
14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>12</b> inches above grade	
15. Well grouted? <input checked="" type="checkbox"/> yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>13</b> ft. to <b>3</b> ft.	
16. Nearest source of possible contamination: ft. <b>100</b> Direction <b>west</b> Type <b>chicken house</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)	
18. Elevation: Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: <b>OWNER WILL INSTALL CONCRETE SLAB</b>
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Brady Water Wells 363</b> Business name License No. Address <b>R2 Box 217A Douglass</b> Signed <b>Richard Brady</b> Date <b>11-7-78</b> Authorized representative	

T 30 S R 3 E 1/4 Sec 14