


17-31-22 E

Company McCune City Water Well  
 (Record from samples of Druggist Rouse)  
 Farm No.

Sec. 17 T. 31 R. 22 E  
 Loc. NE NE  
 County Crawford



Total Depth 1292 1/2  
 Comm. Comp.  
 Shot or Treated  
 Contractor  
 Issued

Casing	
20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation  
 Production

Figures Indicate Bottom of Formation

Soil and clay	6	white flint, lime	760
brown lime	14	soft whitish lime, shaley	770
black lime, shale break	20	gray lime	780
lime	32	white lime, harder	790
light shale	112	gray lime, harder	800
dark shale	119	gray flint, lime, white spar	810
dark shale	129	gray to greenish shale	830 (Hannibal)
dark lime	132	dark lime, some white flint	856
light shale	141	hard white lime and spar	860
dark slate and lime	148	lime, hd. whitish	900
light shale and lime	181	lime	1040
dark shale some gas	186	softer lime	1050
light shale	198	lime	1200
sand, little shale	242	white rounded grain glassy sand	1260
(Bartlesville sand)			
dark shale	249	gray lime, some crystal spar	1280
light shale	255	sand	1290
dark shale	264	sand	1292 1/2
light shale	300		
light sandy shale	315		
dark shale	350		
sand, light to white	360		
sand, darker to brownish	370		
sandy shale	380		
light shale	390		
lime and shale	400		
light shale	410		
dark shale	420		
dark shale	490		
coarse white flint	500	(Cotton Rock)	
hard tight white flint	510		
white to gray flint	540	very little lime	
white flint	660	whitish lime, very hard	
coarser white flint	670		
brown lime, white flint	690		
coarser white flint	720	dark lime	
gray flint, some lime	740		
white gray flint	750		

COPY