


1 LOCATION OF WATER WELL: County: **Chautauqua** Fraction: **SE 1/4 SE 1/4 SW 1/4** Section Number: **6** Township Number: **T 34 S** Range Number: **R 12-E** *EW*

Distance and direction from nearest town or city street address of well if located within city?  
**3 east 1 1/2 south on old hiway**

2 WATER WELL OWNER: **Randy Hatfield**  
 RR#, St. Address, Box #: **419 Main**  
 City, State, ZIP Code: **Sedan, Kansas 67361**  
 Board of Agriculture, Division of Water Resources  
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  
  
 4 DEPTH OF COMPLETED WELL: **82** ft. ELEVATION: **unk**  
 Depth(s) Groundwater Encountered 1. **65** ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL **65** ft. below land surface measured on mo/day/yr **3/12/88**  
 Pump test data: Well water was **72** ft. after **1/2** hours pumping **10** gpm  
 Est. Yield **8/9** gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter **8** in. to **t.d.** ft., and in. to ft.  
 WELL WATER TO BE USED AS:  
 (1 Domestic) 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)  
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well  
 Was a chemical/bacteriological sample submitted to Department? Yes No **X**; If yes, mo/day/yr sample was submitted  
 Water Well Disinfected? Yes **X** No

5 TYPE OF BLANK CASING USED:  
 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued **X** Clamped  
 2 Brass 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded  
 3 Fiberglass Threaded  
 Blank casing diameter **5** in. to **t.d.** ft., Dia. in. to ft., Dia. in. to ft.  
 Casing height above land surface **30** in., weight **160#psi** lbs./ft. Wall thickness or gauge No. **sdr 26**  
 TYPE OF SCREEN OR PERFORATION MATERIAL:  
 1 Steel 3 Stainless steel 5 Fiberglass (7 PVC) 10 Asbestos-cement  
 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)  
 12 None used (open hole)  
 SCREEN OR PERFORATION OPENINGS ARE:  
 1 Continuous slot (3 Mill slot) 5 Gauzed wrapped 8 Saw cut 11 None (open hole)  
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes  
 7 Torch cut 10 Other (specify)  
 SCREEN-PERFORATED INTERVALS: From **71** ft. to **82** ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From **27** ft. to **t.d.** ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: (1 Neat cement) 2 Cement grout 3 Bentonite 4 Other  
 Grout Intervals: From **-4** ft. to **-27** ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination:  
 1 Septic tank 4 Lateral lines 7 Pit privy (10 Livestock pens) 14 Abandoned water well  
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well  
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)  
 13 Insecticide storage  
 Direction from well? **East (not yet built)** How many feet? **75**

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	3	soil			
3	5	sd. silt			
5	65	sd. stone interspaced w/blu to yel clay shale			
65	75	rotten sh. & sd. muddy, multi color soft sh. (water zone)			
75	78	hrd dense blu. lm.			
78	82	sd. sh.			
82	t.d.				
Well was first bailed using 12 gal. bailer for the capacity of the hole, then a 10 g.p.m. sub. pump was instaled and pumped for a period of 2 1/2 hrs. before casing was instaled. Well produced only 7/9 g.p.m. after initial drawdown. A lab test was run by Winfield City Water Dept, indicating 160 PPM total hardness ( 9.3 grains ) 37 PPM chlorides					
An unplugged oil well 1/4 mi W. was pumped and tested at 735 PPM salts at 100 ft.					

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **3/1/88** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **171** This Water Well Record was completed on (mo/day/yr) **3/1/88** under the business name of **G & S Drilling** by (signature) *[Signature]*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.

8810000078-50

OFFICE USE ONLY T R EW SEC.