

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No. _____

1 LOCATION OF WATER WELL: County: Montgomery	Fraction NW ¼ SW ¼ SW ¼	Section Number 31	Township Number T 34 S	Range Number R 17 E
---	-----------------------------------	-----------------------------	----------------------------------	-------------------------------

Distance and direction from nearest town or city street address of well if located within city? **701 Northeast St., Coffeyville, KS**

2 WATER WELL OWNER: KDHE RR#, St. Address, Box # : 1000 SW Jackson blvd City, State, ZIP Code : Topeka KS	Global Positioning System (decimal degrees, min. of 4 digits) Latitude: N 37.03651° Longitude: W 95.59913° Elevation: RIM: 715.33; TOC: 715.03 Datum: WGS84 Data Collection Method: legal survey
--	---

3 LOCATE WELL'S LOCATON WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 15.07 ft.
--	--

N

NW	NE
SW	SE

S

X

Depth(s) Groundwater Encountered 1 _____ ft. 2 _____ ft. 3 _____ ft.

WELL'S STATIC WATER LEVEL **10.57** ft. below land surface measured on mo/day/yr **8/6/14**

Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm

Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feed lot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Domestic (lawn & garden) **10** Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes _____ No **X**; If yes, mo/day/yr

Sample was submitted _____ Water Well Disinfected? Yes _____ No **X**

5 TYPE OF CASING USED:	5 Wrought Iron 8 Concrete tile 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) 2 PVC 4 ABS 7 Fiberglass	CASING JOINTS: Glued _____ Clamped _____ Welded _____ Threaded X
-------------------------------	---	---

Blank casing diameter **2** in. to **5.07** ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.

Casing height below land surface **0.30** ft., Weight _____ lbs./ft. Wall thickness or gauge No. _____

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel 3 Stainless steel 5 Fiberglass **7** PVC 9 ABS 11 Other (specify) _____
 2 Brass 4 Galvanized steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot **3** Mill slot 5 Gauze wrapped 7 Torch cut 9 Drilled holes 11 None (open hole)
 2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw Cut 10 Other (specify) _____

SCREEN-PERFORATED INTERVALS: From **5.07** ft. to **15.07** ft. From _____ ft. to _____ ft.
 From _____ ft. to _____ ft. From _____ ft. to _____ ft.

GRAVEL PACK INTERVALS: From **3** ft. to **15.35** ft. From _____ ft. to _____ ft.
 From _____ ft. to _____ ft. From _____ ft. to _____ ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout **3** Bentonite **4** Other **Concrete: 0-1'**

Grout Intervals From **1** ft. to **3** ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft.

What is the nearest source of possible contamination:

1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage 16 Other (specify below)
 2 Sewer lines 5 Cess pool 8 Sewage lagoon **11** Fuel storage 14 Abandoned water well
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 15 Oil well/ gas well

Direction from well? **NW** How many feet? **~50'**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	15.35	Brown silty clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **8/5/14** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **757**. This Water Well Record was completed on (mo/day/year) **9/3/14** under the business name of **Larsen & Associates, Inc.** by (signature) _____

INSTRUCTIONS: Please fill in blanks or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell>.

TRITERRA LAND SERVICES

KGS Copy

P.O. Box 546
Clearwater, Kansas 67026
Cell (316) 648-3617 Fax (620) 584-4371
E-mail: triterrals@yahoo.com

SURVEYING OF MONITORING WELLS
701 NORTHEAST STREET
COFFEYVILLE, KANSAS

The above site is in Section 31, Township 34 South, Range 17 East of the Sixth Principal Meridian, Montgomery County, Kansas. The Southeast corner of Section 31 was assigned coordinates of 00.00 North and 00.00 West.

The control point from the Jump Start #8 site to the north was used for vertical control. This site's control point was established as a chiseled 'X' on the southeast corner of the old sign base at the north edge of the site.

The Latitude and Longitude were recorded from a GPS device. The site is located on the quad map titled "Coffeyville East".

ID	NORTH	WEST	LATITUDE	LONGITUDE	ELEVATION
SE CORNER 31-34S-17E	00.00	00.00			
(Irregular Section)					
Control Point	894.41	6302.29	37.03682	95.59920	715.94
MW-1 SW NW SW SW	783.46	6349.65	37.03651	95.59936	RIM 715.79 TOC 715.40
MW-2 SW NW SW SW	821.91	6328.66	37.03663	95.59928	RIM 715.86 TOC 715.25
MW-3 SW NW SW SW	777.69	6279.14	37.03651	95.59913	RIM 715.33 TOC 715.03
MW-4 SW NW SW SW	866.67	6336.25	37.03675	95.59932	RIM 716.02 TOC 715.52
MW-5 SW NW SW SW	844.77	6497.14	37.03670	95.59986	RIM 715.25 TOC 714.72
MW-6 SW NW SW SW	753.62	6401.39	37.03645	95.59953	RIM 716.18 TOC 715.63
MW-7 SW NW SW SW	700.08	6333.16	37.03632	95.59937	RIM 715.53 TOC 714.92
MW-8 SW NW SW SW	725.23	6281.97	37.03636	95.59913	RIM 714.83 TOC 714.27

