

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Nemaha

Location listed as:

Section-Township-Range: 35-12E

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): _____

Location changed to:

24-3S-12E

SW SW NW

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: Written description, aerial photos taken in 1942, and mapping tool & aerial photos on KGS website.

initials: DRL date: 5/23/2012

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

? - 3-124 Plotter

J. D. JUDD & SON

CONTRACT DRILLERS

WE SPECIALIZE IN DEEP WATER WELL DRILLING
SUB-SURFACE INFORMATION. Ph. SPRINGDALE 3273

Martin City, Missouri
March 28 1936

Lieut. John H. Sharp
Mo. Dist. C.C.C.
Fort Leavenworth, Kansas.

Log of No. 2 drilled well at CCC Camp Seneca, Kansas.

3'	of soil	black	soft	
29'	of gumbo	black brown	soft	
12'	of sandy gravel	tan	soft	
6"	streak of gravel from 44-45 feet			water level 15' @ 30g.p.m. bailing
5'	of sandy gravel	green	soft	water very weak
Finished @ 50' in dark mud				

6 1/2' of Seneca

Bottom of 8" by 8" screen set @ 44'. Well was drilled with 20" outside casing. After drilling ceased 8" screen and inner casing were installed and centered in the outer casing. The annular space between the two casings was then filled to the surface with pea sized gravel.

J.D. Judd & Son
N.W. Judd
BY N.W. Judd Co. Partner

Copy to Kansas Bureau of Geology