

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: Washington		Fraction NE 1/4 NW 1/4 NW 1/4	Section Number 2	Township Number T 4 S	Range Number R 1 E						
Distance and direction from nearest town or city street address of well if located within city? 12 miles North of Clifton, Ks.			Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: _____ Longitude: _____ Elevation: _____ Datum: _____ Data Collection Method: _____								
2 WATER WELL OWNER: Brad Ohlde RR#, St. Address, Box # : 830 9th Rd. City, State, ZIP Code : Linn, Ks. 66953											
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="text-align: center;">X</td><td></td></tr><tr><td style="text-align: center;">-- NW --</td><td style="text-align: center;">-- NE --</td></tr><tr><td style="text-align: center;">-- SW --</td><td style="text-align: center;">-- SE --</td></tr></table> E S		X		-- NW --	-- NE --	-- SW --	-- SE --	4 DEPTH OF COMPLETED WELL204..... ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... 28 ft. below land surface measured on mo/day/yr. 5/3/07 Pump test data: Well water was..... ft. after..... hours pumping..... gpm Est. Yield 25-30 gpm: Well water was..... ft. after..... hours pumping..... gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering ☒ Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well stock Was a chemical/bacteriological sample submitted to Department? Yes No ☒ ; If yes, mo/day/yr Sample was submitted..... Water well disinfected? Yes ☒ No			
X											
-- NW --	-- NE --										
-- SW --	-- SE --										
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) ☒ PVC 4 ABS 7 Fiberglass Blank casing diameter 5 in. to 94 ft., Diameter. 5 in. to 184 ft., Diameter in. toft. Casing height above land surface..... 12 in., Weight..... 2.37lbs./ft. Wall thickness or gauge No. 214 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass ☒ PVC 9 ABS 11 Other (Specify) 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot ☒ Mill slot 5 Guazed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw Cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From..... 94 ft. to 104 ft., From 184 ft. to 204 ft. From..... 30 ft. to 204 ft., From ft. to ft. GRAVEL PACK INTERVALS: From..... 30 ft. to 204 ft., From ft. to ft. From..... ft. to ft., From ft. to ft.											
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other Grout Intervals: From .. 2 ft. to .. 30 ft., From ft. to ft., From ft. toft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy ☒ Livestock pens 13 Insecticide Storage 16 Other (specify below) 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer Storage 15 Oil well/gas well Direction from well? West How many feet? 500 ..ft.....											
FROM	TO	LITHOLOGIC LOG	FROM	TO	Litho XXXXXXXXXXXXXXX Log						
0	2	Topsoil	210	215	Shale, gray						
2	7	Clay, brown									
7	32	Sandstone & sandrock									
32	64	Shale, gray									
64	66	Rock									
66	98	Shale, red/gray									
98	110	Shale, green/brown									
110	118	Sandstone, tan									
118	188	Shale, gray									
188	210	Sandstone, white/tan									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5/3/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/year) 5/5/07 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i> INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdhe.state.ks.us/geo/waterwells .											