

50

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County BROWN Fraction TRACT Section number 34 Township number T 4 S Range number R 15 E

2. Distance and direction from nearest town or city: 2 MILES NORTH
0.75 MI SE 1/4 MILE EAST NORTH
Street address of well location if in city: (NETAWAKA) SIDE

3. Owner of well: Clifford E Bailey
R.R. or street: RFD 1 NETAWAKA
City, state, zip code: RT 1 Netawaka, Kans 66515

4. Locate with "X" in section below: Sketch map:

1 Mile
N
W
E
S
1 Mile
1 Mile

Sketch map: DRIVE WAY HOUSE SEPTIC TANK CORNER E CLUB

5. Type and color of material

	From	To
Top Soil	0	6
Gray Clay	6	19
Gray Sandy Clay	19	22
Yellow Sandy Clay	22	26
Yellow " " w/med Gravel	26	29
Gray Clay	29	50
med Gravel	50	51
Gray Clay	51	56
lime	56	61
Shale	61	100

6. Bore hole dia. 10 in. Completion date 6-21-76
Well depth 100 ft.

7. Rotary Driven Dug
Hollow rod Jettied Bored Reverse rotary

8. Use: Domestic Public supply Industry
Irrigation Air conditioning Stock
Lawn Oil field water Other

9. Casing: Material PVC Height: Above or below
Threaded Welded Surface 24 in.
RMP PVC 614C Weight 2.75 lbs./ft.
Dia. 5 in. to 100 ft. depth Wall Thickness: inches or
Dia. 5 in. to 100 ft. depth gage No. 258

10. Screen: Manufacturer's name Pumco
Type PVC Dia. 5 in.
Slot/gauze 1025 Length 45 ft.
Set between 20 ft. and 60 ft.
35 ft. and 90 ft.
Gravel pack? Yes Size range of material 10/30 40/60

11. Static water level: 19 ft. below land surface Date 6-21-76 mo./day/yr.

12. Pumping level below land surfaces: Air Test
ft. after hrs. pumping g.p.m.
ft. after hrs. pumping g.p.m.
Estimated maximum yield 3 g.p.m.

13. Water sample submitted: Yes No Date 6-21-76 mo./day/yr.

14. Well head completion: Cap top
Pitless adapter 24 inches above grade

15. Well grouted? Yes
With: Neat cement Bentonite Concrete
Depth: From 0 ft. to 10 ft.

16. Nearest source of possible contamination:
ft. 800 Direction E Type Interd
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name JACUZZI
Model number 534B HP 1/2 Volts 230
Length of drop pipe 90 ft. capacity 10 g.p.m.
Type:
X Submersible Turbine
Jet Reciprocating
Centrifugal Other

18. Elevation: 1120
Topography: Hill Slope Upland Valley

19. Remarks: I WILL PUT CEMENT SLAB
AROUND THE WELL.
Clifford E Bailey

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report
is true to the best of my knowledge and belief.
Business name STRADER DRY CO INC License No. 182
Address RT 1 Holton, KS
Signed Dale Goshen Date 7-1-76
Authorized representative

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

BR = 1064 Σ = 1101