

FRYHID

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: County: <u>Washington</u>	Fraction <u>SE</u> $\frac{1}{4}$ <u>SE</u> $\frac{1}{4}$ <u>SW</u> $\frac{1}{4}$	Section Number <u>29</u>	Township Number <u>T</u> <u>4</u> <u>S</u>	Range Number <u>R</u> <u>4</u> <u>E</u> <u>X</u>
--	---	-----------------------------	---	---

Distance and direction from nearest town or city street address of well if located within city?

4 South, 1 1/2 West Greenleaf

2 WATER WELL OWNER: <u>Melvin Thoms</u> RR#, St. Address, Box #: <u>Route 1</u> City, State, ZIP Code: <u>Greenleaf, Kansas 66943</u>	Board of Agriculture, Division of Water Resources Application Number:
---	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: <u>100</u> ft. ELEVATION: <u>1400</u>
--	--

Depth(s) Groundwater Encountered 1. 40 ft. 2. NA ft. 3. 13 ft.

WELL'S STATIC WATER LEVEL 40 ft. below land surface measured on mo/day/yr 5/18/1982

Pump test data: Well water was NA ft. after NA hours pumping NA gpm

Est. Yield 30 gpm: Well water was NA ft. after NA hours pumping NA gpm

Bore Hole Diameter 8 in. to 100 ft., and NA in. to NA ft.

WELL WATER TO BE USED AS:

5 Public water supply	8 Air conditioning	11 Injection well
X1 Domestic	3 Feedlot	6 Oil field water supply
2 Irrigation	4 Industrial	7 Lawn and garden only
		10 Observation well

Was a chemical/bacteriological sample submitted to Department? Yes NA No X; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes X No NA

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped <u>NA</u>
------------------------------	----------------	-----------------	---

1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded <u>NA</u>
X 2 PVC	4 ABS	7 Fiberglass		Threaded <u>NA</u>

Blank casing diameter 5 in. to 80 ft., Dia. NA in. to NA ft., Dia. NA in. to NA ft.

Casing height above land surface 12 in., weight 3 lbs./ft. Wall thickness or gauge No. 258

TYPE OF SCREEN OR PERFORATION MATERIAL:	X 7 PVC	10 Asbestos-cement
---	---------	--------------------

1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot	3 Mill slot	5 Gauzed wrapped	X 8 Saw cut	11 None (open hole)
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes	
		7 Torch cut	10 Other (specify)	

SCREEN-PERFORATED INTERVALS: From 80 ft. to 100 ft., From NA ft. to NA ft., From NA ft. to NA ft.

GRAVEL PACK INTERVALS: From 14 ft. to 100 ft., From NA ft. to NA ft., From NA ft. to NA ft.

6 GROUT MATERIAL:	X1 Neat cement	2 Cement grout	3 Bentonite	4 Other
-------------------	----------------	----------------	-------------	---------

Grout Intervals: From 4 ft. to 14 ft., From NA ft. to NA ft., From NA ft. to NA ft.

What is the nearest source of possible contamination:

X 1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	

Direction from well? South How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	3	topsoil			
3	6	sandy clay			
6	10	sandrocks			
10	56	blue clay			
56	77	blue clay			
77	80	limestone			
80	96	blue shale			
96	98	limestone			
98	100	blue shale			
100		stop			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>NA</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>5/12/82</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>359</u> This Water Well Record was completed on (mo/day/yr) <u>5/24/82</u> under the business name of <u>Daryl Cox & Sons Inc.</u> by (signature) <u>Daryl Cox</u>
--

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY

T

R

SW

SEC.

29

SE 1/4

SE 1/4

SW 1/4

14