

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Washington	NC $W\frac{1}{2}$ $\frac{1}{4}$ $W\frac{1}{2}$ $\frac{1}{4}$ $E\frac{1}{2}$ $\frac{1}{4}$	35	T 5 S	R 1 EW

Distance and direction from nearest town or city street address of well if located within city?

North edge of Clifton

2 WATER WELL OWNER:	City of Clifton
RR#, St. Address, Box # :	P.O. Box 86
City, State, ZIP Code :	Clifton, KS 66937
	Board of Agriculture, Division of Water Resources Application Number: 43,907 & 35,687

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 120.5 ft. ELEVATION: unknown
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 74 . . . ft. below land surface measured on mo/day/yr Pump test data: Well water was not ch'd . . . ft. after hours pumping gpm Est. Yield unknown gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter. 42 . . . in. to 120 . . . ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes. No. ☒ ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No ☐

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued. Clamped.
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter 10 . . . in. to 98 . . . ft., Dia in. to ft., Dia in. to ft.			
Casing height above land surface. 18 . . . in., weight 40.42 . . . lbs./ft. Wall thickness or gauge No. 365			
TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify) ft.
SCREEN-PERFORATED INTERVALS: From 98 . . . ft. to 119 . . . ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From 60 . . . ft. to 120 . . . ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 0 . . . ft. to 5 . . . ft., From 5 . . . ft. to 25 . . . ft., From 25 . . . ft. to 60 . . . ft.				
What is the nearest source of possible contamination:	10 Livestock pens	14 Abandoned water well		
1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	16 Other (specify below)
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage	None known
Direction from well?		How many feet?		

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil			
3	10	Clay, gray			
10	30	Clay, brown			
30	34	Sand and gravel, dirty			
34	44	Clay			
44	57	Clay and sandstone			
57	58	Iron Rock, hard			
58	75	Sandstone and clay			
75	111	Sandstone, brown			
111	118	Sandstone, reddish brown			
118	120	Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-26-00 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No. 185 This Water Well Record was completed on (mo/day/yr) 7-31-00 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>
--