

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Washington		near 1/4 center 1/4 SE 1/4	5	T 5 S	R 1 E
Distance and direction from nearest town or city street address of well if located within city? 5 miles north and 3 miles West of Clifton, KS					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # :		Application Number: 44,204			
City, State, ZIP Code :		Clifton, KS 66937			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 225 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 62 ... ft. below land surface measured on mo/day/yr 12/13/01 Pump test data: Well water was 115 ... ft. after 2 ... hours pumping 800 ... gpm Est. Yield 800 ... gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter. 28 ... in. to 225 ... ft., and, in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) ☒ Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes. No. ☒ ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No			
		TYPE OF BLANK CASING USED: 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued. ☒ Clamped. 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded ☒ PVC 4 ABS 7 Fiberglass Threaded Blank casing diameter 16 ... in. to 145 ... ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface. 12 ... in., weight 16.15 ... lbs./ft. Wall thickness or gauge No.500			
		TYPE OF SCREEN OR PERFORATION MATERIAL: ☒ PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot ☒ Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) ft.			
		SCREEN-PERFORATED INTERVALS: From. 145 ... ft. to 225 ... ft., From ft. to ft. From. ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From. 22 ... ft. to 225 ... ft., From ft. to ft. From. ft. to ft., From ft. to ft.			
6 GROUT MATERIAL: 1 Neat cement ☒ Cement grout 3 Bentonite 4 Other					
Grout Intervals: From. 1 ... ft. to 22 ... ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination: None within 1/2 mile					
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below) Direction from well? How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	topsoil			
4	18	Clay, brown			
18	60	Clay, yellow and red			
60	75	Sand, creek gravel and gray shale			
75	116	Shale, gray			
116	130	Sandstone with shale layers			
130	165	Sandstone, medium to coarse			
165	175	Shale, gray			
175	214	Sandstone, fine to coarse			
214	225	Limestone			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12/14/01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No. 138 This Water Well Record was completed on (mo/day/yr) 12/13/01 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.					