


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Washington</u>	Fraction <u>SW 1/4 NW 1/4 SE 1/4</u>	Section number <u>10</u>	Township number T <u>5</u> S R <u>1</u> <u>EW</u>
2. Distance and direction from nearest town or city: <u>4 N 1 1/2 W</u> Street address of well location if in city: <u>of Clifton</u>			3. Owner of well: <u>Douglas Kieffer</u> R.R. or street: <u>#1</u> City, state, zip code: <u>Clifton, Kansas 66937</u>		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		
5. Type and color of material			From	To	6. Bore hole dia. <u>20</u> in. Completion date <u>7-19-76</u> Well depth <u>189</u> ft.
<u>top soil + clay</u>			<u>0</u>	<u>86</u>	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
<u>sand rock + clay</u>			<u>86</u>	<u>92</u>	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
<u>sand rock</u>			<u>92</u>	<u>190</u>	9. Casing: Material <u>AC</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>24</u> lbs./ft. Dia. <u>12</u> in. to <u>189</u> ft. depth Wall Thickness, inches or Dia. <u>12</u> in. to <u>189</u> ft. depth gage No. <u>3/4</u>
<u>shale</u>			<u>190</u>		10. Screen: Manufacturer's name <u>Johnson</u> <u>Concrete</u> Type <u>Transit</u> Dia. <u>12</u> Slot/gauge <u>1/8"</u> Length <u>39</u> Set between <u>150</u> ft. and <u>189</u> ft. ft. and <u>189</u> ft. Gravel pack? <u>YES</u> Size range of material <u>1/8-1/4"</u>
					11. Static water level: <u>72</u> ft. below land surface Date <u>11-20-75</u> mo./day/yr.
					12. Pumping level below land surfaces: <u>120</u> ft. after <u>1</u> hrs. pumping <u>850</u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1000</u> g.p.m.
					13. Water sample submitted: <u> </u> Yes <u>X</u> No Date <u> </u> mo./day/yr.
					14. Well head completion: ☐ Pitless adapter <u>12</u> inches above grade
					15. Well grouted? <u>YES</u> With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
					16. Nearest source of possible contamination: <u>NONE</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes <u>X</u> No
					17. Pump: <u> </u> Not installed Manufacturer's name <u>WLR</u> Model number <u>8M</u> HP <u>55</u> Volts <u> </u> Length of drop pipe <u>190</u> ft. capacity <u>800</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second-sheet if needed)					
18. Elevation: <u>1370</u> Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks: 		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Geo Cox & Sons Inc</u> <u>258</u> Business name License No. Address <u>Clifton, Kansas</u> Signed <u>Francis Cox</u> Date <u>1-15-</u> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5