

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County WASHINGTON	Fraction 1/4 CENTER 1/4 SW 1/4	Section number 20	Township number T 5 S	Range number R 1 E/W
2. Distance and direction from nearest town or city: 2 N - 3 E			3. Owner of well: NORMAN NELSON			
Street address of well location if in city: CLIFTON			R.R. or street: RR			
			City, state, zip code: CLIFTON KANSAS 66937			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 20 in. Completion date 6/29/76		
				Well depth 153 ft.		
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From To		8. Use: Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐		
				9. Casing: Material AC Height Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight 30 lbs./ft. Dia. 12 in. to 153 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 34"		
TOPSOIL		0 3		10. Screen: Manufacturer's name JOHNSON CONCRETE		
BROWN CLAY		3 23		Type AC Dia. 12 Slot/gauze 1/8" Length 65		
SANDROCK		23 25		Set between 88 ft. and 153 ft. ☐ ft. and ☐ ft. Gravel pack? YES Size range of material 1/4 X 1/2		
BROWN CLAY		25 36		11. Static water level: 65 ft. below land surface Date 6/29/76 mo./day/yr.		
GRAY CLAY		36 41		12. Pumping level below land surfaces: 150 ft. after 1 hrs. pumping 700 g.p.m.		
RED CLAY		41 46		ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 700 g.p.m.		
GRAY CLAY		46 68		13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.		
SANDROCK		68 153		14. Well head completion: Pitless adapter ☐ ☒ Inches above grade		
BLUE SHALE STOP		153		15. Well grouted? YES With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: ft. 1 MILE Direction SOUTH Type SEPTIC TANK		
				Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: Not installed Manufacturer's name WESTERN LAND PUMP		
				Model number 10-C-H HP 85 Volts ☐		
				Length of drop pipe 145 ft. capacity 700 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other ☐		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
18. Elevation: 1250		19. Remarks:		Geo Cox & Sons Inc 258 Business name CLIFTON, KANSAS License No. ☐ Address Clifton, Kansas Signed David Cox Date 6/29/76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5