

1 LOCATION OF WATER WELL:		Fraction	Section Number		Township Number	Range Number
County: Washington		SE ¼ NE ¼ NE ¼	29		T 5 S	R 1 E
Distance and direction from nearest town or city street address of well if located within city?						
1 North, 2½ West, ¾ North of Clifton						
2 WATER WELL OWNER: Valley View Ranch						
RR#, St. Address, Box # : Clifton, Kansas 66937						Board of Agriculture, Division of Water Resources
City, State, ZIP Code :						Application Number:
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 121 ft. ELEVATION: 1322					
	Depth(s) Groundwater Encountered 1. 60 ft. 2. ft. 3. ft.					
	WELL'S STATIC WATER LEVEL 60 ft. below land surface measured on mo/day/yr 8/16/82					
	Pump test data: Well water was NA ft. after hours pumping gpm					
	Est. Yield 60 gpm: Well water was ft. after hours pumping gpm					
	Bore Hole Diameter 8 in. to 121 ft., and in. to ft.					
	WELL WATER TO BE USED AS: ☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well					
	Was a chemical/bacteriological sample submitted to Department? Yes No ☒ ; If yes, mo/day/yr sample was submitted					
	Water Well Disinfected? Yes ☒ No					
5 TYPE OF BLANK CASING USED:						
1 Steel		3 RMP (SR)		5 Wrought iron		8 Concrete tile
☒ PVC		4 ABS		6 Asbestos-Cement		9 Other (specify below)
				7 Fiberglass		CASING JOINTS: Glued ☒ Clamped ☒
						Welded
						Threaded
Blank casing diameter 5 in. to 91 ft., Dia. in. to ft., Dia. in. to ft.						
Casing height above land surface 12 in., weight 3 lbs./ft. Wall thickness or gauge No. 258						
TYPE OF SCREEN OR PERFORATION MATERIAL:						
1 Steel		3 Stainless steel		5 Fiberglass		8 RMP (SR)
2 Brass		4 Galvanized steel		6 Concrete tile		9 ABS
						10 Asbestos-cement
						11 Other (specify)
						12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:						
1 Continuous slot		3 Mill slot		5 Gauzed wrapped		☒ Saw cut
2 Louvered shutter		4 Key punched		6 Wire wrapped		11 None (open hole)
				7 Torch cut		9 Drilled holes
						10 Other (specify)
SCREEN-PERFORATED INTERVALS: From 91 ft. to 121 ft., From ft. to ft.						
From ft. to ft., From ft. to ft.						
GRAVEL PACK INTERVALS: From 10 ft. to 121 ft., From ft. to ft.						
From ft. to ft., From ft. to ft.						
6 GROUT MATERIAL: ☒ Neat cement 2 Cement grout 3 Bentonite 4 Other						
Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.						
What is the nearest source of possible contamination:						
1 Septic tank		4 Lateral lines		☒ Livestock pens		14 Abandoned water well
2 Sewer lines		5 Cess pool		11 Fuel storage		15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit		12 Fertilizer storage		16 Other (specify below)
				9 Feedyard		13 Insecticide storage
Direction from well? South						How many feet? 100
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	
0	3	topsoil				
3	22	brown clay				
22	60	brown clay w/ sandy clay				
60	125	sandrock				
125	130	hard rock				
130		stop				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8/16/1982 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 359 This Water Well Record was completed on (mo/day/yr) 9/14/1982 under the business name of Daryl Cox & Sons Inc. by (signature) Daryl Cox						
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.						