


USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Washington</u>	Fraction <u>SW 1/4 SE 1/4 SW 1/4</u>	Section number <u>31</u>	Township number <u>T 5 S R 3 E</u>	Range number <u>3</u>
2. Distance and direction from nearest town or city: <u>7 1/2 E of Clifton</u>		3. Owner of well: <u>William Gilbert Palmer, Kansas</u>		R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: 		Sketch map:		6. Bore hole dia. <u>8</u> in. Completion date <u>10-29-77</u> Well depth <u>61</u> ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
<u>Clay</u>		<u>0</u>	<u>15</u>	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>soft sandrock</u>		<u>15</u>	<u>30</u>	9. Casing: Material <u>PVC</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☒ Weight <u>3</u> lbs./ft. Dia. <u>5</u> in. to <u>61</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>61</u> ft. depth gage No. <u>258</u>		
<u>sandrock</u>		<u>30</u>	<u>35</u>	10. Screen: Manufacturer's name <u>Pumpco Supply</u> Type <u>PVC</u> Dia. <u>5</u> Slot/gauze <u>1/16"</u> Length <u>20</u> Set between <u>51</u> ft. and <u>61</u> ft. _____ ft. and _____ ft. Gravel pack? <u>YES</u> Size range of material <u>1/16"-1/4"</u>		
<u>clay</u>		<u>35</u>	<u>40</u>	11. Static water level: _____ mo./day/yr. <u>20</u> ft. below land surface Date <u>10-28-77</u>		
<u>hard rock</u>		<u>40</u>	<u>41</u>	12. Pumping level below land surfaces: <u>60</u> ft. after <u>1/2</u> hrs. pumping <u>4-5</u> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>4-5</u> g.p.m.		
<u>clay</u>		<u>41</u>	<u>55</u>	13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☒ No Date _____		
<u>sandrock</u>		<u>55</u>	<u>57</u>	14. Well head completion: ☐ Pitless adapter <u>12</u> Inches above grade		
<u>clay</u>		<u>57</u>	<u>61</u>	15. Well grouted? <u>YES</u> With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
(Use a second sheet if needed)				16. Nearest source of possible contamination: ft. <u>250</u> Direction <u>NW</u> Type <u>PRIVEY</u> Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation: <u>1375</u> Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Geo Coy & Sons Inc</u> <u>258</u> Business name License No. Address <u>Clifton Kansas</u> Signed <u>Francis Inc</u> Date <u>11-8</u> Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5