

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: Jackson	Fraction NW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$	Section Number 34	Township Number T 6 S	Range Number R 15E E/W
--	--	-----------------------------	---------------------------------	----------------------------------

Distance and direction from nearest town or city street address of well if located within city? $\frac{1}{4}$ miles north of Holton	Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: _____ Longitude: _____ Elevation: _____ Datum: _____ Data Collection Method: _____
2 WATER WELL OWNER: Travis Amon RR#, St. Address, Box # : 24498 Q Rd City, State, ZIP Code : Holton, Ks. 66436	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N <table border="1" style="width:100%; text-align:center; border-collapse: collapse;"><tr><td style="width:25%;">x</td><td style="width:25%;"></td><td style="width:25%;"></td><td style="width:25%;"></td></tr><tr><td>--NW--</td><td>--NE--</td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td>--SW--</td><td>--SE--</td><td></td><td></td></tr></table> S	x				--NW--	--NE--							--SW--	--SE--			4 DEPTH OF COMPLETED WELL 100 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... 20 ft. below land surface measured on mo/day/yr... 8-22-06 Pump test data: Well water was.....ft. after..... hours pumping..... gpm Est. Yield... 5 ...gpm: Well water was.....ft. after..... hours pumping..... gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No x; If yes, mo/day/yr Sample was submitted..... Water well disinfected? Yes x No
x																	
--NW--	--NE--																
--SW--	--SE--																

5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 2 PVC 4 ABS	5 Wrought Iron 8 Concrete tile 6 Asbestos-Cement 9 Other (specify below) 7 Fiberglass	CASING JOINTS: Glued... x ... Clamped..... Welded..... Threaded.....
Blank casing diameter 5 in. to ft., Diameter. in. to ft., Diameter in. to ft. Casing height above land surface..... 24 in., Weight..... 2.82lbs./ft. Wall thickness or guage No. 258		
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass <u>7 PVC</u> 9 ABS 11 Other (Specify) 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole)		
SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Guazed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped <u>8 Saw Cut</u> 10 Other (specify)		
SCREEN-PERFORATED INTERVALS: From..... 60 ft. to 70 ft., From 30 ft. to 40 ft. From..... ft. to ft., From ft. to ft.		
GRAVEL PACK INTERVALS: From..... 23 ft. to 100 ft., From ft. to ft. From..... ft. to ft., From ft. to ft.		

6 GROUT MATERIAL:	1 Neat cement 2 Cement grout <u>3 Bentonite</u> 4 Other
Grout Intervals: From 3 ft. to 23 ft., From ft. to ft., From ft. to ft.	
What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage 16 Other (specify below) 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer Storage 15 Oil well/gas well ditch	
Direction from well? west How many feet? 65	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	top soil	48	58	fine/course sand grey, chert
3	6	brown clay	58	59	grey limestone
6	12	brown fine sand	59	78	grey/brown shale
12	23	brown/tan sandy clay	78	81	grey limestone
23	30	brown fine sand	81	85	grey/red shale
30	34	brown/grey clay	85	86	grey limestone
34	36	brown fine sand	86	88	red shale
36	38	grey clay	88	100	grey shale
38	40	fine/course sand grey / brown			
40	48	grey/brown clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) .. **8-22-06** .. and this record is true to the best of my knowledge and belief.
Kansas Water Well Contractor's License No. **182** This Water Well Record was completed on (mo/day/year) .. **10-26-06**
under the business name of **Strader Drilling Co., Inc.** by (signature) *[Signature]*

INSTRUCTIONS: Use typewriter or ball point pen. *PLEASE PRESS FIRMLY* and *PRINT* clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well. Visit us at <http://www.kdhe.state.ks.us/geo/waterwells>.